

BUTTERNUT LANE STA. 10+00 - 24+00

> HORIZONTAL SCALE: 1" = 50' VERTICAL SCALE: 1" = 5'



DATE 1/27/24	REVISION REMOVED FUTUR	E SENIOR LIVING I
URVEY	RECORD DRAWING	PRELIMINARY
OBCA	☐ FINAL ☐	SKETCH/CONCEPT
ESIGN		
BWC GRT	O'LEARY-	RURKI
RAWN		
GRT	CIVIL ASSOCIA	ATES, PLC
HECKED		
BWC	13 CORPORATE ESSEX JUNCTION.	
CALE	,	
1" = 50'	PHONE: 802-87 FAX: 802-878- E-MAIL: obca@olear	9989

BUILDING PER TOWN OF GEORGIA REVIEW COMMENTS

HOMESTEAD CAMPGROUND

GEORGIA, VERMONT

PLAN & PROFILE

7

THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.



GUIDELINE 7
ISOLATION DISTANCES TO
UNDERGROUND UTILITY SERVICES

PREFERRED 10' OFFSET FROM TREE TRUNK TO UNDERGROUND UTILITY SERVICES

TREE SPACING VARIES AS PER SPECIES

ADJUST AS NEEDED TO MAINTAIN ADEQUATE CLEARANCE TO UTILITY SERVICES

OFFSET TO UNDERGROUND UTILITY SERVICES - SECTION

NOTE: THIS OFFSET GUIDELINE DOES NOT APPLY TO UNDERGROUND UTILITY MAINS INSIDE AND PARALLEL TO THE GREENBELT

OFFSET TO UNDERGROUND UTILITY SERVICES - PLAN

(IN FEET)

1 inch = 50 ft

NOTE: ALWAYS
FIELD VERIFY 'AS BUILT'
LOCATIONS OF UNDERGROUND
UTILITIES PRIOR TO PLANNING
AND PLANTING

GREENBELT

REFER TO RECORD DRAWINGS AND

CALL 'DIGSAFE' TO MARK LOCATIONS

SYMBOL	QUANTITY	COMMON NAME	BOTANIC NAME	SIZE	COST		
	17	LITTLELEAF LINDEN	TILIA CORDATA	2 -2 ½ " CALIPER	\$600 EACH / \$10,200		
A STATE OF THE STA	19	EUROPEAN HORSECHESTNUT	AESCULUS HIPPOCASTANUM	2 -2 ½ " CALIPER	\$600 EACH / \$11,400		
	20	THORNLESS HONEYLOCUST	GLEDITSIA TRIANCANTHOS INERMIS	2 -2 ½ " CALIPER	\$600 EACH / \$12,000		
TOTAL 56; 40' ON CENTER \$33,600							
*NOTE: ALL PLANTING SPECIES MAY BE SUBSTITUTED WITH ALTERNATIVE STREET TREES PER TOWN OF GEORGIA REGULATIONS.							

LANDSCAPING SPECIFICATIONS

ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEEDING AND MULCHING PRIOR TO NOVEMBER 1 OF EACH YEAR. ANY DISTURBED AREAS SHALL BE IMMEDIATELY SEEDED AND MULCHED WITHIN 15 DAYS. ANY WORK PERFORMED AFTER OCTOBER 1 OF EACH YEAR SHALL BE STABILIZED WITH MULCH OR NETTING SUFFICIENT TO PREVENT EROSION AND SHALL BE IMMEDIATELY SEEDED AND REMULCHED AS SOON AS WEATHER PERMITS IN THE SPRING. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM

- 1. SEED MIXTURE IN ALL AREAS SHALL BE URBAN MIX CONFORMING TO THE TABLE SHOWN ON THE PLANS. FOR SEEDING BETWEEN SEPTEMBER 1 AND NOVEMBER 1, WINTER RYE SHALL BE USED AT AN APPLICATION RATE OF 100 POUNDS PER ACRE.
- 2. FERTILIZER SHALL BE STANDARD COMMERCIAL GRADE CONFORMING TO THE STATE FERTILIZER LAW AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. DRY FERTILIZER, IF USED, SHALL BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE. LIQUID FERTILIZER, IF USED, SHALL BE APPLIED IN A 1-2-1 RATIO WITH THE MINIMUM RATE TO INCLUDE 100 POUNDS OF NITROGEN, 200 POUNDS OF PHOSPHATE, AND 100 POUNDS OF POTASH PER ACRE.
- LIMESTONE SHALL CONFORM TO ALL STATE AND FEDERAL REGULATIONS AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. THE LIMESTONE SHALL BE APPLIED AT A RATE OF TWO TONS PER ACRE OR AS DIRECTED.

	URBAN MIX GRAS	SS SEED
% BY WEIGHT	LBS. LIVE SEED PER ACRE	TYPE OF SEED
37.5	45	CREEPING RED FESCUE
31.25	37.5	KENTUCKY BLUEGRASS
31.25	37.5	WINTER HARDY, PERENNIAL RYE
100	120 # LIVE	SEED PER ACRE

DATE 1/27/24	REVISION DEMOVED FLITLIDE SENIOD LIVING BLIII	DINC DED TOWN OF GEODEIA DEVIEW COMMENTS	BY CPT
SURVEY OBCA	REMOVED FUTURE SENIOR LIVING BUIL RECORD DRAWING PRELIMINARY SKETCH/CONCEPT	DING PER TOWN OF GEORGIA REVIEW COMMENTS	DATE 1/18/24
DESIGN BWC GRT DRAWN	O'LEARY-BURKE	HOMESTEAD CAMPGROUND GEORGIA, VERMONT	JOB # 2081-44 FILE
GRT CHECKED	CIVIL ASSOCIATES, PLC		2018-44-23 SHEET#
BWC SCALE 1" = 50'	13 CORPORATE DRIVE ESSEX JUNCTION, VT 05452 PHONE: 802-878-9990 FAX: 802-878-9989 E-MAIL: obca@olearyburke.com	LANDSCAPING PLAN	8

OF 4" OF TOPSOIL AND BE SEEDED, FERTILIZED, LIMED, AND MULCHED IN ACCORDANCE WITH THE FOLLOWING:

4. WITHIN 24 HOURS OF APPLICATION OF FERTILIZER, LIME, AND SEED, THE SURFACE SHALL BE MULCHED WITH A HAY MULCH. MULCH SHALL BE SPREAD UNIFORMLY OVER THE AREA AT A RATE OF TWO TONS PER ACRE OR AS ORDERED BY THE ENGINEER.

URBAN MIX GRASS SEED						
% BY WEIGHT	LBS. LIVE SEED PER ACRE	TYPE OF SEED				
37.5	45	CREEPING RED FESCUE				
31.25	37.5	KENTUCKY BLUEGRASS				
31.25	37.5	WINTER HARDY, PERENNIAL RYE				
100	120 # LIVE SEED PER ACRE					

2 STRAND TWISTED 12 GAUGE

RUBBER HOSE

GAL. WIRE ENCASED IN 1" DIA.

(2 TO 3) 2" X 2"

HARDWOOD STAKES DRIVEN

(MIN. 18") FIRMLY INTO SUB-

GRADE PRIOR TO BACKFILLING,

WHEN REQUIRED (SEE NOTE #2);

STAKE ABOVE FIRST BRANCHES

OR AS NECESSARY FOR FIRM

SUPPORT; STAKES SHALL BE

CAPABLE OF STANDING FIRM

FOR AT LEAST ONE YEAR

FORM 4" SAUCER

UNDISTURBED SOIL

BACKFILL WITH EXCAVATED SOIL

AT A RATE OF 10 POUNDS PER

TAMP TO REMOVE AIR POCKETS

AMENDED WITH 5-10-5 FERTILIZER

CUBIC YARD OF SOIL. WATER AND

TREE PLANTING

1. PLANT TREE SO THAT TOP OF ROOT BALL IS EVEN WITH THE FINISHED GRADE.

3. TREES SHALL BE GUARANTEED FOR A PERIOD OF TWO YEARS AFTER PLANTING.

CONDITIONS AS DETERMINED BY THE PROJECT LANDSCAPE ARCHITECT.

TAPE PRIOR TO PLANTING TO PREVENT GIRDLING.

2. STAKING AS REQUIRED ONLY IN SITUATIONS WHERE TREES WILL BE SUBJECTED TO WINDY

4. EXAMINE ENTIRE TREE AND REMOVE ALL NURSERY TAGS, ROPE, STRING AND SURVEYOR

5. STREET TREES SHALL BE LOCATED AT LEAST 10' FROM THE NEAREST UTILITY SERVICE.

2 X BALL DIA.

— PLUMB TREE TRUNK

3" MULCH - DO NOT

APPLY AROUND TRUNK

- CUT AND REMOVE WIRE

MESH BASKET, ROPE AND/

OR BURLAP WRAP FROM

TOP 1/3 OF ROOTBALL

-BREAK APART EDGE OF

EXCAVATION W/SHOVEL

AND BLEND PLANT MIX

WITH EXISTING SOIL TO

PROVIDE SOIL TRANSITION

018.0114132 THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.

GARAGE

GARAGE

YMBOL | QUANTITY |

GARAGE

TYPICAL FOUNDATION PLANTING PLAN AND 5-PLEX DRIVEWAY DETAIL

COMMON NAME

COMMON NAME

SUMMER WINE NINEBARK

BLUESTAR JUNIPER

GOLDEN PRINCESS SPIREA

—PROPOSED FOUNDATION LANDSCAPE SCHEDULE—

PROPOSED SCREENING LANDSCAPE SCHEDULE -

- 🌕 | 41 | EASTERN WHITE CEDAR | THUJA OCCIDENTALIS| 6 FT | \$300 EA. / \$12,300

--- CONSTRUCT 3" SAUCER RIM AROUND EACH PLANT

____ 3" LAYER OF APPROVED SHREDDED BARK MULCH CONTINUOUS LAYER WHEN USED IN SHRUB BEDS

UNDERLAY WITH BLACK WEED BARRIER FABRIC

SHRUB PLANTING

BOTANIC NAME

HYDRANGEA

SPIRAEA

BOTANIC NAME

GARAGE

TYPICAL FOUNDATION PLANTING (SEE PROPOSED FOUNDATION

LANDSCAPING SCHEDULE ON THIS SHT. FOR SIZE/TYPE)

FOR LOCATIONS & PRÒPOSED TREE

\$60 EA. / \$1,440

5 GAL. \$60 EA. / \$1,440

TOTAL \$12,960

TOTAL \$12,300

LANDSCAPING SCHEDULE ON THIS

SHT. FOR SIZE/TYPE

5 GAL.

HEIGHT

LOOSEN, CUT, & REMOVE

- BACKFILL WITH APPROVED TOPSOIL PLANTING MIXTURE

PLANT SHRUB


GROWN


AT SAME DEPTH

AT WHICH SHRUB HAD PREVIOUSLY

- BURLAP FROM TOP 2/3

OF ROOT BALL






consistent fixture-to-fixture color

Need help? Tech help line: (888) 722-1000 Email: sales@rablighting.com Website: www.rablighting.com

Copyright © 2022 RAB Lighting All Rights Reserved Note: Specifications are subject to change at any time without notice



Page 2 of 3


Need help? Tech help line: (888) 722-1000 Email: sales@rablighting.com Website: www.rablighting.com


Copyright © 2022 RAB Lighting All Rights Reserved Note: Specifications are subject to change at any time without notice


LIGHTING CUT SHEETS

NTS

Page 1 of 3









DATE 1/27/24	REMOVED FUTURE SENIOR LIVING BU	ILDING PER TOWN OF GEORGIA REVIEW COMMENTS	BY GRT
SURVEY OBCA	☐ RECORD DRAWING ☐ PRELIMINARY ☐ FINAL ☐ SKETCH/CONCEPT		DATE 1/18/24
DESIGN BWC GRT	O'LEARY-BURKE	HOMESTEAD CAMPGROUND GEORGIA, VERMONT	JOB# 2081-44
<i>DRAWN</i> GRT	CIVIL ASSOCIATES, PLC	GEONGIA, VERMONI	FILE 2018-44-23
CHECKED BWC SCALE	13 CORPORATE DRIVE ESSEX JUNCTION, VT 05452 PHONE: 802-878-9990 FAX: 802-878-9989 F-MAII: obca@olearyburke.com	LIGHTING PLAN	SHEET#


THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.

12 INCHES BELOW GRAVEL BASE.

- 2. SOIL BORINGS AND TEST PITS ARE RECOMMENDED TO CONFIRM DESIGN CONDITIONS AND APPLICABLE ROADWAY SECTIONS. THE ROADWAY FINISH GRADE SHALL BE AS SHOWN ON THE DRAWING BUT NOT LESS THAN A SLOPE OF 0.5%. 4. IF THE TOP COURSE OF PAVEMENT IS NOT INSTALLED WITHIN 60 DAYS OF THE BASE COURSE, THE CONTRACTOR SHALL APPLY EMULSION TO THE FULL WIDTH OF THE BASE COURSE BEFORE 5. IF LEDGE EXISTS IN A SUBGRADE IT SHALL BE SHATTERED TO
- UNDERDRAINS; UNDERDRAINS SHALL BE CONSTRUCTED ON ALL ROADWAYS AND SHALL FOLLOW THE ROADWAY SLOPE AND DAYLIGHT INTO CATCH BASINS UNLESS OTHERWISE NOTED. 7. ALL HANDICAP RAMPS ARE TO HAVE EXPOSED AGGREGATE SURFACES, WITH 1/4" CURB REVEAL 8. RECREATION PATHS ARE TO CONTINUE AT CONSTANT GRADE ACROSS DRIVEWAYS.
- 9. PAVED PARKING AREAS SHALL BE CONSTRUCTED TO THE SAME CONFIGURATION AS THIS ROADWAY SECTION.

 10. GAS MAIN LOCATED BY VERMONT GAS SYSTEMS. 11. 10' UTILITY EASEMENT FOR POWER, CABLE AND PHONE. ONE
- SIDE ONLY. SEE SITE PLAN. 12. ALL LINES AND MARKINGS TO BE TAPE. 13. ALL INTERSECTIONS WITH STOP CONTROL TO COMPLY WITH 14. THE ROAD WIDTH, GREENBELT WIDTH, AND TYPE OF PEDESTRIAN

WALKWAY SHALL BE DETERMINED FROM THE SITE PLANS.




PAVEMENT 15" CRUSHED RUN GRAVEL BASE (AS PER (VT. STATE SPEC. 704.05 OR 704.06) MIRAFI 500X FABRIC

NOTE: REFER TO SITE PLAN FOR DRIVEWAY WIDTHS

2" THICK TYPE III COURSE BIT. CONC.

DRIVEWAY SECTION

NTS



NOTES:


- 1) CURBING SHALL BE CONSTRUCTED WITH 3,500 PSI (CLASS B) CONCRETE IN 10' SECTIONS WITH 1/8"
- 4) ALL EXPOSED CONCRETE CURB SHALL RECEIVE TWO COATS OF ANTI-SPALLING COMPOUND AFTER THE INITIAL CURING

END AREA = 0.94 S.F.

- JOINTS BETWEEN SECTIONS.
- CURBING EXPANSION JOINTS SHALL BE CONSTRUCTED EVERY 20' AND SHALL BE CONSTRUCTED OF MATERIAL CONFORMING TO AASHTO DESIGNATION M-153 (1/2" SPONGE RUBBER OR CORK).
- 3) PRIOR TO PAVING, THE PORTION OF CURBING TO BE IN CONTACT WITH THE PAVEMENT SHALL BE COATED WITH EMULSIFIED ASPHALT
- PERIOD (APPROXIMATELY 28 DAYS).

CONCRETE CURE NTS

CURBED ROADWAY SECTION



WORKS REQUIREMENTS, THE VERMONT STATE STANDARD SPECIFICATIONS FOR CONSTRUCTION, AND THE APPROVED ENGINEERING PLANS AND SPECIFICATIONS.

2. THE ROAD FINISH GRADE SHALL HAVE A MINIMUM SLOPE OF 0.5%.


ALL WORK SHALL BE PERFORMED IN ACCORDANCE WITH THE TOWN PUBLIC

PRIOR TO PLACEMENT OF GRAVEL, A MINIMUM OF ONE (1) GRADATION TEST SHALL BE PERFORMED AT THE CONTRACTOR'S EXPENSE FOR EACH DIFFERENT BASE MATERIAL USED EVERY 500' SECTION OF ROAD. A COMPACTION TEST SHALL ALSO BE PERFORMED AT THE CONTRACTOR'S IF THE TOP COURSE OF PAVEMENT IS NOT INSTALLED WITHIN 60 DAYS OF EXPENSE EVERY 200' SECTION OF ROAD OR MORE OFTEN IF THE TEST THE BASE COURSE, THE CONTRACTOR SHALL APPLY EMULSION TO THE FAILS TO MEET THE COMPACTION REQUIREMENTS. THE TEST LOCATIONS FULL WIDTH OF THE BASE COURSE BEFORE INSTALLING THE TOP COURSE. SHALL BE SELECTED BY THE ENGINEER.

UNCURBED ROADWAY SECTION

YELLOW OR ORANGE WARNING TAPE SHALL BE BURIED 15" ABOVE

ALL GAS, ELECTRIC, TELEPHONE AND T. V. LINES.



1. CONCRETE SHALL HAVE A MINIMUM STRENGTH OF 3,500 PSI AT 28 DAYS AND SHALL BE AIR ENTRAINED WITH AN ADMIXTURE PRODUCING AN AIR CONTENT OF 5% TO 7% BY VOLUME.

FEET. CURB AND SIDEWALK SECTIONS SHALL BE SEPARATED BY A PREMOLDED JOINT FILLER. 3. AFTER THE INITIAL CURING PERIOD IS OVER (APPROXIMATELY 28 DAYS), ALL EXPOSED SURFACES SHALL RECEIVE TWO COATS OF ANTI-SPALLING COMPOUND.

2. HALF INCH (1/2") TRANSVERSE EXPANSION JOINTS SHALL BE PLACED AT INTERVALS NOT EXCEEDING


TWENTY FEET (20'). SIDEWALKS SHALL BE SCORED TO A DEPTH OF ONE INCH (1") EVERY FIVE (5')

4. SEE WRITTEN SPECIFICATION FOR APPROVED CONSTRUCTION METHODS AND MATERIAL REQUIREMENTS.

5. SIDEWALK BASE SHALL BE VT SPEC. 704.05A OR APPROVED EQUAL

6. SIDEWALKS AT RESIDENTIAL DRIVEWAY CROSSING SHALL BE AT LEAST 8" THICK. 7. WHEN CONNECTING NEW SIDEWALK TO AN EXISTING SIDEWALK, STEEL DOWELS SHALL BE DRILLED INTO THE EXISTING SIDEWALK A MINIMUM OF 6" AND SHALL EXTEND INTO THE NEW SIDEWALK A MINIMUM OF 6".

TYPICAL SIDEWALK SECTION




1) CURB CUT WIDTHS SHALL BE AS FOLLOWS SINGLE DRIVE: 15 FEET (MIN.) DOUBLE DRIVE: 20 FEET (MAX., 45 FEET (MAX.) COMMERCIAL DRIVE:

2) DRIVE WIDTHS SHALL BE AS FOLLOWS SINGLE DRIVE: 10 FEET (MIN.) DOUBLE DRIVE: 15 FEET (MAX.) COMMERCIAL DRIVE: 40 FEET (MAX.)

3) ALL APRONS WITHIN PUBLIC RIGHTS-OF-WAY SHALL BE PAVED. 4) APRON SUBBASE SHALL MATCH THE ROADWAY SUBBASE FOR MATERIALS AND THICKNESS.

5) CURBING EXPANSION JOINTS SHALL BE CONSTRUCTED BETWEEN DRIVE APRON AND CURB.

DRIVEWAY APRON



- 1. THE FABRIC SHALL BE PULLED AROUND THE PIPE AND WRAPPED WITH DUCT TAPE OR WIRE TO PROVIDE A TIGHT ANCHOR.
- 2. CAST IN PLACE RUBBER BOOTS SHALL BE USED AROUND ALL STRUCTURE PENETRATIONS.

ROADWAY UNDERDRAIN

NTS



PRELIMINARY SKETCH/CONCEPT O'LEARY-BURKE CIVIL ASSOCIATES, PLC 13 CORPORATE DRIVE ESSEX JUNCTION. VT 05452 PHONE: 802-878-9990 FAX: 802-878-9989 E-MAIL: obca@olearyburke.com

HOMESTEAD CAMPGROUND GEORGIA, VERMONT

ROADWAY DETAILS

THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.

GENERAL CONSTRUCTION SPECIFICATIONS

VERMONT AGENCY OF TRANSPORTATION STANDARD SPECIFICATIONS FOR CONSTRUCTION, THE

2. THE CONTRACTOR SHALL CONTACT ALL UTILITIES BEFORE EXCAVATION TO VERIFY THE LOCATION OF

ANY UNDERGROUND LINES. THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-344-7233

AND MAY OR MAY NOT BE EITHER ACCURATE OR COMPLETE. CONTRACTOR SHALL VERIFY THE

VEGETATION, PAVEMENT AND STRUCTURES NECESSARY TO CONSTRUCT THIS PROJECT UNLESS OTHERWISE NOTED ON THESE PLANS. THE CONTRACTOR SHALL REMOVE ALL EXCESS MATERIAL

DEBRIS AND TRASH FROM THE SITE UPON COMPLETION OF CONSTRUCTION, UNLESS OTHERWISE

CREATED AS A RESULT OF CONSTRUCTION DOES NOT CREATE A NUISANCE OR A SAFETY HAZARD.

REQUIRED TO WET SECTIONS OF THE CONSTRUCTION AREA WITH WATER, APPLY CALCIUM CHLORIDE

5. THE CONTRACTOR SHALL BE RESPONSIBLE AT HIS OWN EXPENSE FOR ENSURING THAT THE DUST

ANY SURFACES, LINES, OR STRUCTURES WHICH HAVE BEEN DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED TO THE CONDITION AT LEAST EQUAL TO THAT IN WHICH THEY

THE DESIGN ON THESE PLANS SHALL BE INSPECTED BY O'LEARY-BURKE CIVIL ASSOCIATES,

REQUIREMENTS. O'LEARY- BURKE WAIVES ANY AND ALL RESPONSIBILITY AND LIABILITY FOR PROBLEMS THAT MAY ARISE FROM THE FAILURE OF THE CONTRACTOR TO FOLLOW THESE PLANS, SPECIFICATIONS AND THE DESIGN INTENT THAT THE PLANS CONVEY, AND FROM FAILURE TO HAVE

8. FOR ANY WORK WITHIN THE HIGHWAY RIGHT-OF-WAY A MINIMUM OF ONE-WAY TRAFFIC SHALL BE MAINTAINED AT ALL TIMES. CONTINUOUS TWO-WAY TRAFFIC WILL BE REQUIRED AT NIGHT, DURING PEAK-HOURS, AND WHENEVER POSSIBLE DURING ACTUAL CONSTRUCTION ACTIVITIES. UNIFORMED TRAFFIC CONTROL OFFICERS SHALL DIRECT TRAFFIC DURING PEAK HOURS WHEN THERE IS ONE-WAY

TRAFFIC OR WHEN DEEMED NECESSARY BY THE TOWN OR STATE. TEMPORARY CONSTRUCTION SIGNS AND TRAFFIC CONTROL SIGNS SHALL BE ERECTED BY THE CONTRACTOR IN ACCORDANCE

TO ENSURE COMPLIANCE WITH THE PLAN(S), THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND THE TOWN OF ESSEX PUBLIC WORKS DEPARMENT 24 HOURS IN ADVANCE OF STARTING ANY WORK,

10. THE HORIZONTAL AND VERTICAL SEPARATION FOR SEWER AND WATER LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF THE "TEN STATE STANDARDS - RECOMMENDED

11. TOPSOIL SHALL BE STOCKPILED, SEEDED, AND MULCHED UNTIL REUSED. SILT FENCES SHALL BE

12. HEALTHY EXISTING TREES ON AND ADJACENT TO THE SITE SHALL BE SAVED AND PROTECTED AS

13. OPEN CUT AREAS SHALL BE MULCHED OUTSIDE OF ACTUAL WORK AREAS, AND BEST MANAGEMENT

14. AT COMPLETION OF GRADING, SLOPES, DITCHES, AND ALL DISTURBED AREAS SHALL BE SMOOTH

TOPSOIL AND BE FERTILIZED, SEEDED, LIMED, AND MULCHED. TURF ESTABLISHMENT SHALL BE

PERFORMED IN ACCORDANCE WITH SECTION 651 OF THE VERMONT HIGHWAY DEPARTMENT

16. ALL FILL SHALL BE PLACED IN 6 INCH LIFTS AND THOROUGHLY COMPACTED TO 95% OF MAXIMUM

17. DRAINAGE COURSES AND STREAMS SHALL BE CONTROLLED IN DISTURBED CONSTRUCTION AREAS

15. FINISH SLOPES, DITCHES AND DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4 INCHES OF

DENSITY AT OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D698 STANDARD

SEEDING AND MULCHING DIRECTLY UPON COMPLETION OF CONSTRUCTION; CONSTRUCTION OF EROSION CONTROL DEVICES AS DIRECTED BY THE ENGINEER.

18. THE SILT FENCES, DITCHES, AND OTHER EROSION CONTROL DEVICES, SHALL BE INSPECTED,

ENGINEER UNTIL ALL DISTURBED AREAS HAVE BEEN GRASSED AND APPROVED BY THE

MAINTAINED AND REPAIRED BY THE CONTRACTOR AFTER EVERY RAINFALL OR AS ORDERED BY THE

20. ALL WORK INCLUDING BUT NOT LIMITED TO SHALL CONFORM TO THE WILLISTON PUBLIC WORKS STANDARD

ENGINEER. THE MAINTENANCE OF THE EROSION CONTROL DEVICES WILL INCLUDE REMOVAL OF

19. PRIOR TO CONSTRUCTION, ALL MATERIALS SHALL BE APPROVED BY THE ENGINEER. ALL MATERIALS

TO BE TAKEN OVER BY THE TOWN SHALL BE APPROVED BY THE PUBLIC WORKS DEPARMENT.

AND FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE.

SPECIFICATIONS AND THE SPECIFICATIONS INCLUDED ON THESE PLANS.

A) PRESERVING NATURAL VEGETATION WHENEVER POSSIBLE: AVOIDING UNECESSARY DISTURBANCE OF SOILS; EARLY INSTALLATION OF STORM PIPES AND DITCHES;

PRACTICES SHALL BE EMPLOYED TO CONFINE SHEET WASH AND RUNOFF TO THE IMMEDIATE OPEN

AREA AS ORDERED BY THE ENGINEER. THE CONTRACTOR SHALL REFERENCE ALL STORMWATER BMP'S

PLACED AND STAKED CONTINUOUSLY AROUND THE BOTTOM OF THE TOPSOIL PILES.

CUTTING THE PAVEMENT, BEGINNING THE INSTALLATION OF ANY UTILITIES, BRINGING IN ANY NEW

WHERE AND WHEN DEEMED NECESSARY BY THE ENGINEER, THE CONTRACTOR SHALL BE

OR SWEEP ASPHALT ROADS WITH A POWER BROOM AS DUST CONTROL.

WERE FOUND IMMEDIATELY PRIOR TO THE BEGINNING OF OPERATIONS.

BEEN NOTIFIED TO INSPECT THE WORKS AND TESTS IN PROGRESS.

GRAVEL FOR THE NEW BASE, PAVING, AND FINAL INSPECTION.

ESSEX JUNCTION, VERMONT, TO ENSURE COMPLIANCE WITH THE PLANS AND

EXACT LOCATION OF EXISTING UTILITIES AND SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ANY

UTILITY, PUBLIC OR PRIVATE, SHOWN OR NOT SHOWN HEREON. CONTRACTOR SHALL CONNECT OR RECONNECT ALL UTILITIES TO THE NEAREST SOURCE THROUGH COORDINATION WITH UTILITY OWNER.

1. ALL WORK AND MATERIALS SHALL BE APPROVED BY AND IN ACCORDANCE WITH THE LATEST

MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, THE TOWN SPECIFICATIONS AND

AND THE TOWN OF ESSEX PUBLIC WORKS DEPARMENT PRIOR TO ANY EXCAVATION.

3. UTILITIES INFORMATION SHOWN HEREON WERE OBTAINED FROM BEST AVAILABLE SOURCE

4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DEMOLITION AND REMOVAL OF ALL EXISTING

DIRECTED BY THE ENGINEER.

WITH STATE AND TOWN STANDARDS.

STANDARDS FOR WATER."

ORDERED BY THE ENGINEER.

PROVIDED BY THE STATE OF VERMONT

PROCTOR, UNLESS OTHERWISE SPECIFIED.

BY THE FOLLOWING METHODS:

ANY ACCUMULATED SEDIMENTATION.

SPECIFICATIONS

REQUIREMENTS, THE WRITTEN TECHNICAL SPECIFICATIONS, AND THESE PLANS.

SEWAGE DESIGN INFORMATION

- . IT IS THE OPINION OF THE ENGINEER THAT THE SOIL CONDITIONS WITHIN THE PROPOSED SEWAGE DISPOSAL AREAS MEET THE STATE OF VERMONT EPR RULES & ARE SUITABLE FOR CONVENTIONAL SEWAGE DISPOSAL AS SHOWN ON THIS
- 2. THE SEWAGE DISPOSAL SYSTEM SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE TOWN OF COLCHESTER REGULATIONS AND THE VERMONT ENVIRONMENTAL
- 3. THE FOLLOWING MINIMUM ISOLATION DISTANCES SHALL BE MAINTAINED FROM THE



4. BASIS OF DESIGN:

DESIGN FLOW:

DISPOSAL AREA TO:

TYPICAL 3-BEDROOM SINGLE-FAMILY HOME SEWAGE SYSTEM: APPLICATION RATE (FINE SAND): 1.0 GAL/DAY/SF REQUIRED ABSORPTION AREA: 420 SF 420 GPD / 1.0 GAL/DAY/SF =PROPOSED PRIMARY SYSTEM:


THREE (3) TRENCHES @ 4 FT X 35 FT = 420 SF PROVIDED PROPOSED INTER-FINGERED REPLACEMENT AREA: THREE (3) TRENCHES @ 4 FT X 35 FT = 420 SF PROVIDED TWO (2) 3-BEDROOM SINGLE-FAMILY HOME SHARED SEWAGE SYSTEM:

APPLICATION RATE (FINE SAND): 1.0 GAL/DAY/SF REQUIRED ABSORPTION AREA: 840 GPD / 1.0 GAL/DAY/SF = 840 SF PROPOSED PRIMARY SYSTEM: THREE (3) TRENCHES @ 4 FT X 70 FT = 840 SF PROVIDED PROPOSED INTER-FINGERED REPLACEMENT AREA: THREE (3) TRENCHES @ 4 FT X 70 FT = 840 SF PROVIDED

5. SEPTIC TANK: 3-BEDROOM HOME DESIGN FLOW = 420 GPD > 560 GPD = 1,000 GAL (2) 3-BEDROOM HOME SHARED SYSTEM = 840 GPD X 2 = 1,680 GAL MIN.


A. USE 1,000 GALLON (TYPICAL S.F. HOME) AND 2,000 GALLON (SHARED SYSTEM) PRECAST CONCRETE SEPTIC TANKS. CAMP PRECAST OR APPROVED EQUAL. WITH TWO ACCESS COVERS; 4,000 PSI CONCRETE; WATERPROOF JOINTS AND SET ON THOROUGHLY COMPACTED SUBBASE. THE OUTLET BAFFLE SHALL HAVE AN EFFLUENT FILTER.

B. THE USE OF GARBAGE DISPOSALS IS NOT ALLOWED.




TYPICAL CONCRETE SEPTIC TANK

NTS




TYPICAL GRAVITY DISTRIBUTION BOX NTS




THE PIPE. IN NO CASE SHALL DEPTH OF FORCEMAIN COVER BE LESS THAN 3'. BUILDING SEWER SHALL HAVE A MIN. DEPTH OF COVER OF 2'.

TYPICAL SEWER & FORCEMAIN TRENCH




SEWER CLEANOUT DETAIL




ABSORPTION TRENCH (CONVENTIONAL SYSTEM) (LOTS 1, 2, AND 3)

TABLE A -	SEWAGE	SYS	TEM	INVER'	T EL	EVATIO	ONS KE	EY				
OVOTEM	HOUSE		SEPTIC TANK	<	D-	BOX			TRENCH L	ATERALS		
SYSTEM	4" OUTLET	4" INLET	4" OUTLET	(2) COVERS	4" INLET	4" OUTLETS	#1 (PRIMARY)	#2 (REPLACEMENT)	#3 (PRIMARY)	#4 (REPLACEMENT)	#5 (PRIMARY)	#6 (REPLACEMENT)
LOT 8 INDIVIDUAL SEWAGE SYSTEM	387.5' (MIN.)	387.25	387.0'	* 390.0'	386.8'	386.7	386.5'	386.5'	386.5'	386.5'	386.5'	386.5'
LOT 9 INDIVIDUAL SEWAGE SYSTEM	387.5' (MIN.)	387.25	387.0'	* 390.0'	386.8'	386.7'	386.5'	386.5'	386.5'	386.5'	386.5'	386.5'
LOT 10 INDIVIDUAL SEWAGE SYSTEM	387.0' (MIN.)	386.75	386.5	* 390.0'	386.3'	386.2'	386.0'	386.0'	386.0'	386.0'	386.0'	386.0'
LOT 11 INDIVIDUAL SEWAGE SYSTEM	386.5' (MIN.)	386.25	386.0'	* 390.0'	375.8'	375.7'	385.5'	385.5'	385.5'	385.5'	385.5'	385.5'
LOT 12 SHARED SEWAGE SYSTEM	387.0' (MIN.)	386.75	386.5	* 390.0'	386.3'	386.2'	386.0'	386.0'	386.0'	386.0'	386.0'	386.0'
LOT 13 SHARED SEWAGE SYSTEM	387.0' (MIN.)	386.75	386.5'	* 390.0'	386.3'	386.2'	386.0'	386.0'	386.0'	386.0'	386.0'	386.0'
	•			* COVERS	TO BE SET	3"-6" ABOVE	E EXISTING GRO	UND.				



TYPICAL 3-BEDROOM SINGLE-FAMILY HOME SEWAGE DISPOSAL SYSTEM LAYOUT



TWO (2) SINGLE-FAMILY HOME SHARED SEWAGE DISPOSAL SYSTEM LAYOUT

THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.

GENERAL SPECIFICATIONS

- 1. ALL WORK AND MATERIALS SHALL BE IN ACCORDANCE WITH THE LATEST AGENCY OF NATURAL RESOURCES STANDARDS, 10-STATE STANDARDS, AWWA STANDARDS, AND THESE PLANS AND SPECIFICATIONS.
- 2. THE CONTRACTOR SHALL BE RESPONSIBLE AT HIS OWN EXPENSE FOR ENSURING THAT THE DUST CREATED AS A RESULT OF CONSTRUCTION DOES NOT CREATE A NUISANCE OR A SAFETY HAZARD. WHERE AND WHEN DEEMED NECESSARY BY THE ENGINEER, THE CONTRACTOR WILL BE REQUIRED TO WET SECTIONS OF THE CONSTRUCTION AREA WITH WATER OR APPLY CALCIUM CHLORIDE OR SWEEP THE ROADWAY WITH A POWER BROOM AS DUST CONTROL.
- 3. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEEDING AND MULCHING PRIOR TO OCTOBER 1 OF EACH YEAR. ANY DISTURBED AREAS OUTSIDE THE ROADWAY SHALL BE IMMEDIATELY SEEDED AND MULCHED WITHIN 15 DAYS. ANY WORK PERFORMED AFTER OCTOBER 1 OF EACH YEAR SHALL BE STABILIZED WITH MULCH AND NETTING SUFFICIENT TO PREVENT EROSION AND SHALL BE IMMEDIATELY SEEDED AND REMULCHED AS SOON AS WEATHER PERMITS IN THE SPRING.
- THE CONTRACTOR SHALL ENCLOSE THE TRUNKS OF LARGE TREES NEAR THE NEAR THE NEW CONSTRUCTION WITH SNOW FENCING TO PROTECT THE TREES FROM INJURY BY EQUIPMENT.
- 5. ALL SLOPES, DITCHES, AND DISTURBED AREAS SHALL BE GRADED SMOOTH AND BE FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE.
- 6. ALL FILL OR BACKFILL SHALL BE PLACED IN 6 INCH LIFTS AND THOROUGHLY COMPACTED TO 95% OF MAXIMUM DENSITY OF OPTIMUM MOISTURE CONTENT AS DETERMINED BY ASTM D698 STANDARD PROCTOR.
- 7. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4 INCHES OF TOPSOIL AND BE SEEDED, FERTILIZED, LIMED, AND MULCHED IN ACCORDANCE WITH THE FOLLOWING:
- A) SEED MIXTURE IN ALL AREAS SHALL BE URBAN MIX CONFORMING TO THE TABLE TO THE RIGHT. FOR SEEDING BETWEEN SEPTEMBER 1 AND OCTOBER 1, WINTER RYE SHALL BE USED AT A RATE OF 100 LBS PER
- B) FERTILIZER SHALL BE STANDARD COMMERCIAL GRADE CONFORMING TO THE STATE FERTILIZER LAW AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. DRY FERTILIZER IF USED, SHALL BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE LIQUID FERTILIZER, IF USED, SHALL BE APPLIED IN A 1-2-1 RATIO WITH THE MINIMUM RATE TO INCLUDE 100 POUNDS OF NITROGEN, 200 POUNDS OF PHOSPHATE, AND 100 POUNDS OF POTASH PER ACRE.
- C) LIMESTONE SHALL CONFORM TO ALL STATE AND FEDERAL REGULATIONS AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. THE LIMESTONE SHALL BE APPLIED AT A RATE OF ONE TON PER ACRE AS DIRECTED.
- D) WITHIN 24 HOURS OF APPLICATION OF FERTILIZER, LIME, AND SEED, THE SURFACE SHALL BE MULCHED WITH A HAY MULCH. MULCH SHALL BE SPREAD UNIFORMLY OVER THE AREA AT A RATE OF TWO TONS PER ACRE AS ORDERED BY THE ENGINEER
- E) ALL TURF ESTABLISHMENT SHALL BE PERFORMED IN ACCORDANCE WITH THE VERMONT STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 651.
- F) TOPSOIL SHALL BE STOCKPILED, SEEDED, AND MULCHED UNTIL REUSED. HAYBALES SHALL BE PLACED AND STAKED CONTINUOUSLY AROUND THE BOTTOM OF THE TOPSOIL PILES.

STAKE-OUT REQUIREMENTS

THE SEWAGE SYSTEM LOCATIONS SHALL BE STAKED OR VERIFIED BY O'LEARY-BURKE CIVIL ASSOCIATES, PLC. PRIOR TO CONSTRUCTION

TESTING REQUIREMENTS

THE CONTRACTOR SHALL FURNISH ALL FACILITIES AND PERSONNEL FOR

CONDUCTING THE FOLLOWING TESTS: STRUCTURES TEST:

THE SEPTIC TANKS SHALL BE TESTED BY FILLING WITH WATER TO A POINT ONE (1) FOOT BELOW THE ACCESS LID UNLESS A TOP JOINT TANK IS USED. A STABILIZATION PERIOD OF ONE (1) HOUR SHALL BE PROVIDED TO ALLOW FOR ABSORPTION. AT THE END OF THE STABILIZATION PERIOD, THE STRUCTURES SHALL BE REFILLED IF NECESSARY TO ONE (1) FOOT BELOW THE ACCESS LID AND THE TEST PERIOD OF 24 HOURS SHALL BEGIN. AT THE END OF THE TEST THERE SHALL BE NO VISIBLE OR MEASURABLE EXFILTRATION OR INFILTRATION, OR THE TEST SHALL BE CONSIDERED FAILED. IF THE TEST FAILS, THE CONTRACTOR SHALL REPAIR OR WATERPROOF AND RE-TEST AT NO EXTRA EXPENSE TO THE OWNER.

FORCE MAIN PRESSURE TEST:

THE PVC FORCE MAIN SHALL BE FILLED WITH WATER AND TESTED BY THE CONTRACTOR TO A MINIMUM PRESSURE OF 50 PSI AT THE HIGHEST POINT ALONG THE FORCE MAIN FOR TWO HOURS AND THE PRESSURE SHALL NOT VARY MORE THAN 5 PSI. THE NEW LINES SHALL NOT BE ACCEPTED IF THE LEAKAGE DURING THE TWO-HOUR TEST IS GREATER THAN THAT DETERMINED BY THE FOLLOWING FORMULA:

L = THE ALLOWABLE LEAKAGE IN GALLONS PER HOUR $L = ND\sqrt{P}$ 7.400

N = THE NUMBER OF JOINTS IN THE LENGTH OF PIPELINE D = THE NOMINAL DIAMETER OF THE PIPE IN INCHES

P = THE AVERAGE TEST PRESSURE DURING THE LEAKAGE

TEST IN POUNDS PER SQUARE INCH LEAKAGE IS DEFINED AS THE QUANTITY OF WATER THAT MUST BE SUPPLIED INTO THE NEWLY LAID PIPE TO MAINTAIN THE PRESSURE OF 50 PSI. THE

ACCEPTABLE LIMIT AT NO EXTRA CHARGE TO THE OWNER. PUMP STATION TEST (LOTS 4, 5, 6, 7, AND 8): THE CONTRACTOR AND THE ENGINEER SHALL BE PRESENT DURING START-UP. THE CONTRACTOR SHALL PROVIDE A WATER SOURCE TO PERFORM A FULL OPERATIONAL CHECK OF THE STATION, INCLUDING ALL FLOAT FUNCTIONS AND ALARM TESTING. THE PUMP SHALL BE FIELD-TESTED TO INSURE THE

CONTRACTOR SHALL AT ONCE LOCATE ANY LEAKS AND ACHIEVE THE

TESTED TO PUMPING CAPACITY MEETS THE PROJECT REQUIREMENTS. DISTRIBUTION LINES TEST (LOTS 4, 5, 6, 7, AND 8): THE ENGINEER MUST PERFORM A PRESSURE AND DISTRIBUTION TEST OF THE LATERALS BEFORE COVERING. AFTER DRILLING THE HOLES AS SPECIFIED & BEFORE TURNING ORIFICES DOWNWARD & INSTALLING ORIFICE SHIELDS, THE UNIFORMITY & HEIGHT SHALL BE TESTED. WHILE PRESSURIZED BY THE PUMP STATION. THE HEIGHT OF THE WATER COLUMN BEING DISCHARGED FROM EACH HOLE WILL BE MEASURED TO VERIFY ADEQUATE PRESSURE AND EVEN DISTRIBUTION. WATER COLUMNS 2.3 FT OR HIGHER WILL CONSTITUTE A PASSING TEST.

PRESSURIZED SYSTEM CONSTRUCTION REQUIREMENTS

1. THE OULET PIPE FROM THE SEPTIC TANK TO THE PUMP STATION SHALL BE 4" SDR 35 PVC, AT A MINIMUM SLOPE OF 1/8"/FT. THE PIPE SHALL BE LAID ON UNDISTURBED GROUND OR . WHEN THE TRENCHES HAVE BEEN EXCAVATED, THE SIDES AND BOTTOM SHALL BE RAKED TO LOOSEN ANY SMEARED SOIL SURFACES.

3. CONSTRUCTION EQUIPMENT SHALL BE KEPT OFF THE AREA TO BE USED FOR SEWAGE DISPOSAL AS MUCH AS POSSIBLE TO PREVENT COMPACTION OF THE SOILS. 4. PLACEMENT OF CRUSHED STONE IN THE TRENCHES SHALL BE INITIATED IMMEDIATELY AFTER TRENCH EXCAVATION IS COMPLETED. THIS WILL REQUIRE THAT THE ENGINEER & AUTHORIZED TOWN INSPECTOR BE PRESENT AT THE TIME OF COMPLETION OF TRENCH EXCAVATION (SEE INSPECTION SPECIFICATIONS).

5. 12" OF CLEAN CRUSHED STONE (1 TO 1-1/2 INCHES) SHALL BE PLACED IN THE BOTTOM OF THE TRENCHES IN ACCORDANCE WITH THE PLANS. THE DISTRIBUTION LINE SHALL BE CAREFULLY PLACED ON THE BEDDING AT A UNIFORM SLOPE (1/8 INCH PER 10 FEET) AND COVERED WITH AT LEAST 2 INCHES OF STONE. THE ENDS OF THE DISTRIBUTION LINES SHALL BE CAPPED. 6. THE GRADING SHALL DIRECT RUN-OFF AWAY FROM THE SEPTIC SYSTEM AREAS AND BE SMOOTH AND FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE. SEE TESTING REQUIREMENTS #4 FOR LATERAL DISCHARGE REQUIREMENTS

CONVENTIONAL SYSTEM CONSTRUCTION REQUIREMENTS

- THE OULET PIPE FROM THE SEPTIC TANK TO THE DISTRIBUTION BOX SHALL BE 4" SDR 35 PVC, AT A MINIMUM SLOPE OF 1/8"/FT. THE PIPE SHALL BE LAID ON UNDISTURBED GROUND OR PROPERLY BEDDED.
- 2. A DISTRIBUTION BOX SHALL BE INSTALLED BETWEEN THE SEPTIC TANK AND THE ABSORPTION TRENCHES. THE DISTRIBUTION BOX SHALL BE SET LEVEL, ON UNDISTURBED GROUND TO EVENLY DISTRIBUTE THE EFFLUENT TO EACH DISTRIBUTION LINE. ADEQUATE PROVISIONS SHALL
 BE TAKEN TO ASSURE THE STABILITY AND ACCESSIBILITY OF THE
 DISTRIBUTION BOX FOR INSPECTIONS. LEVELNESS OF THE DISTRIBUTION BOX SHALL BE WITNESSED BY THE ENGINEER & AN AUTHORIZED TOWN REPRESENTATIVE.
- EACH DISTRIBUTION LINE SHALL CONNECT INDIVIDUALLY TO THE DISTRIBUTION BOX AND EXIT AT THE SAME SLOPE FOR THE FIRST 5 FEET TO 10 FEET. THE PIPE CONNECTING THE DISTRIBUTION BOX TO THE DISTRIBUTION LINES SHALL BE WATERTIGHT AND LAID ON UNDISTURBED GROUND OR PROPERLY BEDDED.
- WHEN THE TRENCHES HAVE BEEN EXCAVATED, THE SIDES AND BOTTOM SHALL BE RAKED TO LOOSEN ANY SMEARED SOIL SURFACES.
- CONSTRUCTION EQUIPMENT SHALL BE KEPT OFF THE AREA TO BE USED FOR SEWAGE DISPOSAL AS MUCH AS POSSIBLE TO PREVENT COMPACTION
- 6. PLACEMENT OF CRUSHED STONE IN THE TRENCHES SHALL BE INITIATED IMMEDIATELY AFTER TRENCH EXCAVATION IS COMPLETED. THIS WILL REQUIRE THAT THE ENGINEER & AUTHORIZED TOWN INSPECTOR BE PRESENT AT THE TIME OF COMPLETION OF TRENCH EXCAVATION (SEE INSPECTION SPECIFICATIONS).
- 7. 12" OF CLEAN CRUSHED STONE (1 TO 1-1/2 INCH) SHALL BE PLACED IN THE BOTTOM OF THE TRENCHES IN ACCORDANCE WITH THE PLANS. THE DISTRIBUTION LINE SHALL BE CAREFULLY PLACED ON THE BEDDING AT A UNIFORM SLOPE (1/8 INCH PER 10 FEET) AND COVERED WITH AT LEAST 2 INCHES OF STONE. THE ENDS
- OF THE DISTRIBUTION LINES SHALL BE CAPPED 8. THE GRADING SHALL DIRECT RUN-OFF AWAY FROM THE SEPTIC SYSTEM AREAS AND BE SMOOTH AND FREE OF POCKETS WITH SUFFICIENT SLOPE TO ENSURE DRAINAGE

INSPECTION REQUIREMENTS


- THE CONTRACTOR SHALL NOTIFY THE ENGINEER & AUTHORIZED TOWN INSPECTOR A MINIMUM OF 24 HOURS IN ADVANCE FOR INSPECTION OF THE BOTTOM OF THE TRENCHES PRIOR TO PLACEMENT OF STONE AND PIPING.
- THE CONTRACTOR SHALL NOTIFY THE ENGINEER & AUTHORIZED TOWN INSPECTOR A MINIMUM OF 24 HOURS IN ADVANCE FOR INSPECTION OF THE SYSTEM PRIOR TO BACKFILLING, INCLUDING THE DISTRIBUTION BOX (LOTS 2, 3 & 4 AND LOT 6 REPLACEMENT AREA) LEVELNESS CHECK & SEPTIC TANK.
- THIS DESIGN MUST BE INSPECTED BY O'LEARY-BURKE CIVIL ASSOCIATES, PLC ESSEX JUNCTION, VERMONT TO ENSURE COMPLIANCE WITH THESE PLANS, O'LEARY-BURKE CIVIL ASSOCIATES WAIVES ANY AND ALL RESPONSIBILTY AND LIABILITY FOR PROBLEMS THAT ARISE FROM FAILURE TO FOLLOW FAILURE TO FOLLOW SPECIFICATIONS, AND THE DESIGN INTENT THAT THE THE PLANS CONVEY, AND FROM FAILURE TO HAVE BEEN NOTIFIED BY THE CONTRACTOR FOR INSPECTIONS.

OPERATION & MAINTENANCE RECOMMENDATIONS

- 1. THE SEPTIC TANK'S PURPOSE IS TO SETTLE OUT SOLIDS, CONTAIN THE SCUM AND PASS TREATED EFFLUENT. BACTERIA WITHIN THE SEPTIC TANK HELPS DECOMPOSE THE SOLIDS. SHOULD ANY SOLIDS PASS THROUGH THE SEPTIC TANK INTO THE SYSTEM, PREMATURE CLOGGING OF THE PIPING, STONE OR NATIVE SOIL BENEATH THE SYSTEM IS LIKELY TO OCCUR. ONLY HUMAN WASTES SHOULD ENTER THE SEWAGE SYSTEM, WATER USE SHOULD BE CONSERVATIVE AND CLEANING AGENTS CAN NOT ENTER THE
- THE STATE FLOW FIGURES OF ARE BASED ON SHORT TERM PEAK USE PERIODS (IE. DAILY EVENTS). ACTUAL FLOWS FOR A 4 BEDROOM HOME SHOULD AVERAGE 175 - 225 GALLONS PER DAY.
- ONCE PER YEAR, THE DEPTH OF SCUM AND SLUDGE IN THE SEPTIC TANK SHOULD BE MEASURED AND THE TANK SHALL BE PUMPED IF:
- A) THE SLUDGE LEVEL IS WITHIN 12 INCHES OF THE BOTTOM OF THE INLET TEE.
- B) THE SCUM LAYER IS WITHIN 3 INCHES OF THE TOP OF THE OUTLET TEE.
- C) IF A OR B IS ANTICIPATED TO OCCUR PRIOR TO THE NEXT INSPECTION. D) IN ANY CASE, THE TANK SHALL BE PUMPED AT A MAXIMUM 5 YEAR INTERVAL.
- ONCE A YEAR, THE DISTRIBUTION BOX SHOULD BE INSPECTED AND ANY SETTLED SOLIDS REMOVED.
- ONCE A YEAR, THE PUMP STATION (LOTS 5-8) SHOULD BE INSPECTED FOR PROPER OPERATION AND SETTLED SOLIDS REMOVED, IF ANY.
- ABOVE ITEMS 1 5 ARE INTENDED TO PROLONG THE LIFE OF THE SYSTEM, NOT GUARANTEE IT. A PROPERLY OPERATED & MAINTAINED SYSTEM GENERALLY FUNCTIONS PROPERLY FOR 8 - 25 YEARS.



DATE	REVISION
SURVEY OBCA DESIGN	☐ RECORD DRAWING ☐ PRELIMINARY ☐ SKETCH/CONCEPT
BWC GRT DRAWN GRT	O'LEARY-BURKE CIVIL ASSOCIATES, PLC
BWC SCALE 1" = 40'	13 CORPORATE DRIVE ESSEX JUNCTION, VT 05452 PHONE: 802-878-9990 FAX: 802-878-9989 E-MAIL: obca@olearyburke.com



AND OPERATION AND MAINTENANCE MANUALS. TESTING DATA A. FORCE MAIN PRESSURE TEST: ALL FORCE MAINS SHALL BE PRESSURE TESTED TO NOT LESS THAN 50 PSI AT THE HIGHEST POINT OF THE TEST SECTION. THE TEST SHALL BE OF A TWO HOUR DURATION AND THE TEST PRESSURE SHALL NOT VARY BY MORE THAN +/- 5 PSI. A LEAKAGE TEST SHALL BE PERFORMED CONCURRENTLY WITH THE PRESSURE TEST. THE ALLOWABLE LEAKAGE SHALL BE DETERMINED BY THE FOLLOWING FORMULA: WHERE L = THE ALLOWABLE LEAKAGE IN GALLONS PER HOUR, N IS THE NUMBER OF JOINTS, D IS THE NOMINAL DIAMETER OF THE PIPE IN INCHES, AND P IS THE AVERAGE TEST PRESSURE IN PSI. B. VALVE PIT AND PUMP THE STRUCTURES SHALL BE TESTED IN THE PRESENCE OF THE ENGINEER FOR EXFILTRATION BY FILLING THE STRUCTURES STATION TEST: TO 1' BELOW THE ACCESS LID. A STABILIZATION PERIOD OF 1 HR SHALL BE PROVIDED TO ALLOW FOR ABSORPTION. AT THE END OF THE STABILIZATION PERIOD THE STRUCTURES SHALL BE REFILLED IF NECESSARY AND THE TEST PERIOD OF 48 HOURS SHALL BEGIN. AT THE END OF THE TEST PERIOD, THERE SHALL BE NO VISIBLE OR MEASURABLE EXFILTRATION OR INFILTRATION OR THE TEST FAILS. IF THE TEST FAILS, THE CONTRACTOR SHALL REPAIR OR WATERPROOF AND C. PUMP STATION: AN AUTHORIZED REPRESENTATIVE OF THE PUMP MANUFACTURER OR AN ELECTRICIAN FAMILIAR WITH THE OPERATION AND SETTING OF THE PUMP STATION AND THE ENGINEER SHALL BE PRESENT DURING STARTUP. AMPERAGE READINGS ON EACH MOTOR LEAD SHALL BE MEASURED AND RECORDED. THE CONTRACTOR SHALL PROVIDE A WATER SOURCE TO PERFORM A FULL OPERATIONAL CHECK OF THE STATION INCLUDING ALL FLOAT FUNCTIONS, ALARM TESTING, INDICATOR LIGHTS, H-O-A SWITCHES, PUMP ALTERNATOR AND PHASE MONITOR IF THREE PHASE PUMPS ARE USED. THE CONTROL SYSTEM SHALL BE CYCLED THROUGH MORE THAN ONCE TO INSURE PROPER SEQUENCING AND OPERATION OF THE PUMPS. EACH PUMP SHALL BE FIELD TESTED TO INSURE THE PUMPING CAPACITY MEETS THE PROJECT REQUIREMENTS. D. ENGINEER SHALL BE GIVEN AT LEAST 24 HOURS NOTICE PRIOR TO TESTING.

PUMP STATION 'A' DATA

 $\frac{1}{440}$ X 4 = 16.43 GPM

20.0 FT

6.16 GPM

LOGIC; AUTOMATIC PUMP ALTERNATOR; 115 VAC CONTROL CIRCUIT; INDIVIDUAL PUMP RUN INDICATOR LIGHTS; INDIVIDUAL H-O-A

SWITCHES; 115 VAC ALARM LIGHT AND HORN MOUNTED ON TOP OF PANEL; 0-5 SEC ADJUSTABLE TIME DELAY FOR EACH PUMP; PANEL

HEATER WITH THERMOSTAT; INDIVIDUAL CIRCUIT BREAKERS FOR EACH

ONE SPARE; INDIVIDUAL ELAPSED TIME METERS. ALL ELECTRIC WIRING

FLOAT HANGER BRACKET, CHECK VALVES, GATE VALVES

PUMP. CONTROL CIRCUIT TRANSFORMER IF REQUIRED, HEATER, AND

SHALL MEET THE REQUIREMENTS OF THE NATIONAL ELECTRIC CODE.

 $\frac{3,313 \text{ GFD}}{(16 \text{ HR/DAY})} \times 4 \text{ HR/DAY} = 1,479 \text{ GALLONS}$

= 3,465 GPD

= 2,450 GPD

= 5,915 GPD


A. TOTAL DESIGN FLOW (USING EPR RULES):

STATIC LIFT (389' - 382') FRICTION LOSSES MINOR LOSSES


TOTAL HEAD LOSS

5,915 GPD =

PRESSURE HEAD TO BE MAINTAINED




PUMP STATION 'A' DETAIL



DATE	REVISION	
SURVEY	☐ RECORD DRAWING ■ PRELIMINARY	
OBCA	☐ FINAL ☐ SKETCH/CONCEPT	,
DESIGN		
BWC GRT	O'LEARY-BURKE	_
DRAWN		
GRT	CIVIL ASSOCIATES, PLC	
CHECKED	44.000000475.00045	_
BWC	13 CORPORATE DRIVE ESSEX JUNCTION. VT 05452	F
SCALE	PHONE: 802-878-9990	_
1" = 40'	FAX: 802-878-9989	
1 - 40	E-MAIL: obca@olearyburke.com	

PUMP STATION 'B' DATA

A. FORCE MAIN PRESSURE TEST: ALL FORCE MAINS SHALL BE PRESSURE TESTED TO NOT LESS THAN 50 PSI AT THE HIGHEST POINT OF THE TEST SECTION. THE TEST SHALL BE OF A TWO HOUR DURATION AND THE TEST PRESSURE SHALL NOT VARY BY MORE THAN +/- 5 PSI. A LEAKAGE TEST SHALL BE PERFORMED CONCURRENTLY WITH THE PRESSURE TEST. THE ALLOWABLE LEAKAGE SHALL BE DETERMINED BY THE FOLLOWING FORMULA: WHERE L = THE ALLOWABLE LEAKAGE IN GALLONS PER HOUR, N IS THE NUMBER OF JOINTS, D IS THE NOMINAL DIAMETER OF THE PIPE IN INCHES, AND P IS THE AVERAGE TEST PRESSURE IN PSI. B. VALVE PIT AND PUMP THE STRUCTURES SHALL BE TESTED IN THE PRESENCE OF THE ENGINEER FOR EXFILTRATION BY FILLING THE STRUCTURES STATION TEST: TO 1' BELOW THE ACCESS LID. A STABILIZATION PERIOD OF 1 HR SHALL BE PROVIDED TO ALLOW FOR ABSORPTION. AT THE END OF THE STABILIZATION PERIOD THE STRUCTURES SHALL BE REFILLED IF NECESSARY AND THE TEST PERIOD OF 48 HOURS SHALL BEGIN. AT THE END OF THE TEST PERIOD, THERE SHALL BE NO VISIBLE OR MEASURABLE EXFILTRATION OR INFILTRATION OR THE TEST FAILS. IF THE TEST FAILS, THE CONTRACTOR SHALL REPAIR OR WATERPROOF AND C. PUMP STATION: AN AUTHORIZED REPRESENTATIVE OF THE PUMP MANUFACTURER OR AN ELECTRICIAN FAMILIAR WITH THE OPERATION AND SETTING OF THE PUMP STATION AND THE ENGINEER SHALL BE PRESENT DURING STARTUP. AMPERAGE READINGS ON EACH MOTOR LEAD SHALL BE MEASURED AND RECORDED. THE CONTRACTOR SHALL PROVIDE A WATER SOURCE TO PERFORM A FULL OPERATIONAL CHECK OF THE STATION INCLUDING ALL FLOAT FUNCTIONS, ALARM TESTING, INDICATOR LIGHTS, H-O-A SWITCHES, PUMP ALTERNATOR AND PHASE MONITOR IF THREE PHASE PUMPS ARE USED. THE CONTROL SYSTEM SHALL BE CYCLED THROUGH MORE THAN ONCE TO INSURE PROPER SEQUENCING AND OPERATION OF THE PUMPS. EACH PUMP SHALL BE FIELD TESTED TO INSURE THE PUMPING CAPACITY MEETS THE PROJECT REQUIREMENTS. D. ENGINEER SHALL BE GIVEN AT LEAST 24 HOURS NOTICE PRIOR TO TESTING.



PUMP STATION 'B' DETAIL



DATE	REVISION				
SURVEY	☐ RECOF	RD DRAWING	PRELIMINARY		
OBCA	☐ FINAL		SKETCH/CONCEPT	-	
DESIGN					<i></i>
BWC GF	ธไ∩'⊺	FARY	-BURK	\mathbf{F}	
DRAWN					
GRT	CIVI	L ASSOC	IATES, PLO	C .	
CHECKED		40.000000			_
BWC		13 CORPORA			F
SCALE		PHONE: 802	,		-
1" = 40'		FAX: 802-8			
1 - 40	l l	E-MAIL: obca@ol	earyburke.com		

A. TYPES OF PIPE

TYPES OF PIPE WHICH SHALL BE USED FOR THE VARIOUS PARTS OF WORK ARE AS FOLLOWS GRAVITY SEWERS SHALL BE PVC SOLID WALL PIPE MEETING ASTM SPECIFICATIONS D-3034 OR F679. B. PVC SEWER PIPE

PVC SEWER PIPE SHALL CONFORM IN ALL RESPECTS TO THE LATEST REVISION OF ASTM SPECIFICATIONS D-3034 OR F679, TYPE PSM POLYVINYL CHLORIDE (PVC) SEWER PIPE AND FITTINGS, SDR35. WALL THICKNESS OF ALL PVC SHALL MEET ASTM SPECIFICATIONS FOR SDR35 PIPE. ALL PIPE AND FITTINGS SHALL BE CLEARLY MARKED AS FOLLOWS:

> MANUFACTURER'S NAME AND TRADEMARK NOMINAL PIPE SIZE MATERIAL DESIGNATION 12454C PVC LEGEND "TYPE PSM SDR35 PVC SEWER PIPE" OR DESIGNATION ASTM D-3034 OR F679

MEASURED AS DESCRIBED BELOW, SHALL BE LESS THAN FIVE PERCENT (5%).

JOINTS SHALL BE PUSH-ON TYPE USING ELASTOMERIC GASKETS AND SHALL CONFORM TO ASTM D-3212. THE GASKETS SHALL BE FACTORY INSTALLED.

THE PIPE SHALL BE FURNISHED IN NOMINAL 13 FOOT LENGTHS. SUFFICIENT NUMBERS OF SHORT LENGTHS AND FULL MACHINE FITTINGS SHALL BE PROVIDED FOR USE AT MANHOLES, CHIMNEYS, AND CONNECTIONS. ALL CONNECTIONS WILL REQUIRE THE USE OF MANUFACTURED FITTINGS. FIELD FABRICATED, SADDLE-TYPE CONNECTIONS WILL NOT BE CONSIDERED ACCEPTABLE

ANY PIPE OR FITTING HAVING A CRACK OR OTHER DEFECT OR WHICH HAS RECEIVED A SEVERE BLOW SHALL BE MARKED REJECTED AND REMOVED AT ONCE FROM THE WORK SITE. ALL FIELD CUTS ARE TO BE MADE WITH SAW AND 90 DEGREE MITRE BOX. BEVEL THE CUT END TO THE SAME AS THE FACTORY BEVEL AND REMOVE ALL INTERIOR BURRS. MEASURE AND PLACE A HOMING MARK ON THE PIPE BEFORE ASSEMBLING. THE PIPE INSTALLED UNDER THIS SPECIFICATION SHALL BE INSTALLED SO THAT THE INITIAL DEFLECTION,

DEFLECTION TESTS SHALL BE PERFORMED ON ALL FLEXIBLE PIPE AFTER THE FINAL BACKFILL HAS BEEN IN PLACE FOR AT LEAST 30 DAYS. THE DEFLECTION TEST SHALL BE RUN USING A RIGID BALL OR MANDREL HAVING A DIAMETER EQUAL TO 95 PERCENT OF THE INSIDE DIAMETER OF THE PIPE. NO MECHANICAL PULLING DEVICES SHALL BE USED DURING THE DEFLECTION TESTS. ALL PIPE NOT MEETING THE DEFLECTION TEST SHALL BE REEXCAVATED AND REPLACED AT THE CONTRACTOR'S EXPENSE.

THE MANHOLE WATER STOP GASKET AND STAINLESS STEEL CLAMP ASSEMBLY MUST BE APPROVED BY THE ENGINEER PRIOR TO THE INSTALLATION OF ANY PIPE.

THE CONTRACTOR WILL SUBMIT CERTIFICATION THAT THE MATERIALS OF CONSTRUCTION HAVE BEEN SAMPLED, TESTED, AND INSPECTED, AND THAT THEY MEET ALL THE REQUIREMENTS—INCLUDING WALL THICKNESS—IN ACCORDANCE WITH ASTM C-3034 OR ASTM F679 FOR ALL PIPE AND FITTINGS TO BE INCLUDED IN THE

PVC PIPE SHALL NOT BE INSTALLED WHEN THE TEMPERATURE DROPS BELOW 32 DEGREES FAHRENHEIT OR GOES ABOVE 100 DEGREES FAHRENHEIT. DURING COLD WEATHER, THE FLEXIBILITY AND IMPACT RESISTANCE OF PVC PIPE IS REDUCED.

EXTRA CARE IS REQUIRED WHEN HANDLING PVC PIPE DURING COLD WEATHER. PVC PIPE SHALL NOT BE STORED OUTSIDE AND EXPOSED TO PROLONGED PERIODS OF SUNLIGHT AS PIPE DISCOLORATION AND REDUCTION IN PIPE IMPACT STRENGTH WILL OCCUR. CANVAS OR OTHER OPAQUE MATERIAL SHALL BE USED TO COVER PVC PIPE

E. MANHOLES

THE CONTRACTOR SHALL CONSTRUCT REINFORCED CONCRETE MANHOLES AND DROP MANHOLES TO THE DIMENSIONS AT THE LOCATIONS SHOWN ON THE CONTRACT DRAWINGS. ALL PRECAST REINFORCED CONCRETE MANHOLE SECTIONS SHALL CONFORM TO THE LATEST VERSION OF THE ASTM SPECIFICATIONS C478. THE EXTERIOR OF THE MANHOLE SHALL BE COATED WITH A WATERPROOF SEALANT.

CONNECTED, AND ANY CHANGE IN SIZE OR DIRECTION SHALL BE GRADUAL AND EVEN.

THE FOOTING SHALL BE CLASS B PRECAST CONCRETE AND SHALL CONFORM TO THE DIMENSIONS INDICATED ON THE PLANS.

SHELVES SHALL BE CONSTRUCTED WITH HARDENED RED SEWER BRICK. ALL BRICK SHALL BE TYPE SS MEETING THE STANDARDS IN ASTM C32. INVERTS FOR SEWER MANHOLES SHALL BE AS SHOWN ON THE PLANS AND DETAILS. INVERTS SHALL HAVE THE EXACT SHAPE OF THE SEWER TO WHICH THEY ARE

ALL CONSTRUCTION OF SEWER MANHOLES MUST BE CARRIED OUT TO ENSURE WATERTIGHT WORK. ANY LEAKS IN MANHOLES SHALL BE CAULKED AND COMPLETELY REPAIRED TO THE SATISFACTION OF THE ENGINEER OR THE ENTIRE STRUCTURE SHALL BE REMOVED AND REBUILT. REPAIRS SHALL ONLY BE ALLOWED TO THE EXTERIOR OF THE

ALL MANHOLES ARE TO BE PROVIDED WITH COPOLYMER POLYPROPYLENE PLASTIC RUNGS WITH STEEL REINFORCEMENT TWELVE INCHES (12") ON CENTER. ALL MANHOLES SHALL BE PROVIDED WITH TOUGH, GRAY CAST IRON MANHOLE FRAMES AND COVERS. ALL IRON CASTINGS SHALL BE THOROUGHLY CLEANED AND THEN COATED WITH HOT TAR BEFORE BEING DELIVERED. FRAMES AND COVERS SHALL BE LEBARON LC 266 TYPE C, OR AN APPROVED EQUAL, AND HAVE A MINIMUM WEIGHT OF 400 POUNDS. MANHOLE COVERS SHALL HAVE THE

PRECAST RISERS AND BASES FOR MANHOLES SHALL CONFORM TO ASTM SPECIFICATIONS C-361. THE PIPE OPENING IN THE PRECAST MANHOLE RISER SHALL HAVE A CAST-IN-PLACE FLEXIBLE GASKET OR AN EQUIVALENT SYSTEM FOR PIPE INSTALLATION AS APPROVED BY THE ENGINEER. JOINTS BETWEEN MANHOLE RISERS SHALL BE RUBBER "O" RING SEALS OR SOFT BUTYL JOINT SEALER (ROPE FORM).

THE MANHOLE COVER FRAMES SHALL BE SET TO FINAL GRADE ONLY AFTER THE BASE COURSE PAVING HAS BEEN COMPLETED. MANHOLES SHALL BE CONSTRUCTED TO GRADE WITH AT LEAST TWO, AND NOT MORE THAN FIVE, COURSES OF BRICK. WITH THE EXCEPTION OF INVERTS, ALL SURFACES OF MANHOLE BRICKWORK SHALL BE PLASTERED WITH CEMENT MORTAR, THE PLASTER BEING CARRIED UP AS THE BRICKWORK PROGRESSES, AND ALL MANHOLE LIFT HOLES SHALL BE GROUTED INSIDE AND OUT WITH EXPANDABLE GROUT.

MANHOLES SHALL BE PLACED AT ALL CHANGES IN SLOPE, SIZE, ALIGNMENT OF PIPE, AT THE ENDS OF EACH LINE, AND AT LEAST EVERY 300 FEET.

EACH BRICK SHALL BE WETTED AND COMPLETELY BEDDED IN MORTAR AT ITS BOTTOM, SIDES, AND ENDS IN ONE OPERATION WITH CARE BEING TAKEN TO FILL EVERY JOINT. BRICKWORK SHALL BE WELL-BONDED, AND JOINTS SHALL BE AS CLOSE AS PRACTICABLE. NO BRICK MASONRY SHALL BE LAID IN WATER NOR SHALL ANY WATER BE ALLOWED TO RISE ON OR AROUND ANY BRICK MASONRY UNTIL IT HAS SET AT LEAST 24 HOURS. NO MASONRY

THE BRICK FOR ORDINARY BRICKWORK SHALL BE COMMON HARD-BURNED CLAY BRICK. ALL BRICK SHALL BE REGULAR AND UNIFORM IN SHAPE AND SIZE WITH PLANE, PARALLEL BEDS, AND FACES. ORDINARY BRICK SHALL CONFORM TO ASTM SPECIFICATION C-32, LATEST VERSION, AND SHALL BE GRADE SS.

BRICK MASONRY SHALL BE LAID IN PORTLAND CEMENT MORTAR COMPOSED OF ONE PART PORTLAND CEMENT AND TWO PARTS OF SAND, MEASURED BY VOLUME, TO WHICH NOT MORE THAN 10 POUNDS OF LIME SHALL BI ADDED FOR EACH BAG OF CEMENT. WATER FOR MORTAR SHALL BE CLEAN AND ONLY AN AMOUNT SUFFICIENT TO PRODUCE A WORKABLE MORTAR SHALL BE USED. MORTAR SHALL BE USED WITHIN ONE HOUR FROM THE TIME THE

THE SAND FOR MORTAR FOR BRICK MASONRY SHALL BE UNIFORMLY GRADED, CLEAN, SHARP, AND CONTAIN NO GRADES LARGER THAN WILL PASS A ONE-EIGHTH INCH (1/8") MESH SCREEN.

CONSTRUCTION METHODS:

EXCAVATIONS SHALL BE MADE TO A POINT AT LEAST SIX INCHES (6") BELOW THE PIPE INVERT TO ACCOMMODATE THE BEDDING MATERIAL. ALL EXCAVATIONS ARE TO BE KEPT DRY WHILE PIPE IS BEING LAID AND UNTIL EACH JOINT AND PIPE HAS BEEN INSPECTED BY THE ENGINEER AND APPROVAL GIVEN TO COMMENCE

B. LAYING SEWER PIPE:

THE BELL END OF THE PIPE SHALL FACE UPGRADE AT ALL TIMES AND BE PLACED IN SUCH A POSITION AS TO MAKE THE INVERT EVEN WHEN THE SUCCEEDING SECTION IS INSERTED. WHERE REQUIRED BY ADVERSE GRADING CONDITIONS, THE CONTRACTOR SHALL FILL ANY GULLY TO MAKE A SUITABLE BEDDING FOR THE SEWER PIPE. THE FILL SHALL BE PNEUMATICALLY COMPACTED TO A 95 PERCENT DRY DENSITY BY THE AASHTO—T—99, METHOD A (STANDARD PROCTOR) TEST, UPON WHICH THE SIX INCHES (6") OF BEDDING MATERIAL SHALL BE PLACED.

ANY PIPE WHICH IS NOT LAID TO GRADE AND ALIGNMENT SHALL BE RELAID TO THE SATISFACTION OF THE ENGINEER. THE BEDDING MATERIAL SHALL BE PLACED AND COMPACTED ON EACH SIDE OF THE PIPE TO A HEIGHT EQUAL TO ONE-HALF THE PIPE DIAMETER AND FOR THE FULL WIDTH OF THE EXCAVATED TRENCH AND AS SHOWN ON THE ACCEPTED PLANS.

BACKFILL SHALL CONSIST OF APPROVED MATERIAL PLACED IN SIX INCH (6") LAYERS WITH EACH LAYER BEING THOROUGHLY COMPACTED TO NOT LESS THAN 95 PERCENT OF MAXIMUM DRY DENSITY AS DETERMINED BY THE AASHTO-T-99 STANDARD PROCTOR BY MEANS APPROVED BY THE ENGINEER.

THE BACKFILL SHALL BE BROUGHT UP EVENLY ON BOTH SIDES OF THE PIPE FOR ITS FULL LENGTH. WALKING OR

BE PERMITTED UNTIL THE TRENCH HAS BEEN BACKFILLED TO A HEIGHT OF AT LEAST TWO FEET (2') ON THE TOP OF HE PIPES. DURING CONSTRUCTION, ALL OPENINGS TO THE PIPELINES SHALL BE PROTECTED FROM THE ENTERING OF EARTH OR OTHER MATERIALS. THE CONTRACTOR SHALL CONTACT THE TOWN OF ESSEX PRIOR TO BACKFILLING ANY NEW SEWER

WORKING ON THE COMPLETED PIPELINE, EXCEPT AS MAY BE NECESSARY IN TAMPING OR BACKFILLING, SHALL NOT

INFRASTRUCTURE FOR INSPECTION AND APPROVAL.

D. CONCRETE CRADLE AND ENCASEMENT FOR PIPE:

WHERE REQUIRED ON THE PLANS OR AS DIRECTED BY THE ENGINEER, A CONCRETE CRADLE SHALL BE USED TO BOLSTER AND STRENGTHEN PIPE. WHERE REQUIRED ON THE PLANS OR AS DIRECTED BY THE ENGINEER, CONCRETE ENCASEMENT OR SEWER WILL BE MADE TO PROTECT NEARBY WELLS OR WATERLINES FOR STREAM CROSSINGS OR FOR SIMILAR PURPOSES. ALL CONCRETE WILL BE CLASS B AS DEFINED IN THE VERMONT STANDARD SPECIFICATIONS FOR CONSTRUCTION, SECTION 501, AND WILL MEET THE REQUIREMENTS OF THAT SECTION.

E. FROST PROTECTION FOR SHALLOW SEWERS:

SEWERS WITH LESS THAN FIVE AND ONE-HALF FEET (5 1/2') OF COVER OVER THE CROWN OR WHERE INDICATED ON THE PLANS SHALL BE PROTECTED AGAINST FREEZING BY INSTALLATION OF TWO, 2" THICK (4" TOTAL) STYROFOAM SM INSULATING SHEETS WITH A TOTAL WIDTH OF FOUR FEET (4') OR TWICE THE PIPE DIAMETER, WHICHEVER IS GREATER. THE SHEETS SHALL BE PLACED SIX INCHES (6") ABOVE THE CROWN OF THE SEWER AFTER COMPACTION OF THE SIX INCH LIFT IMMEDIATELY ABOVE THE CROWN. CARE SHALL BE EXERCISED BY THE CONTRACTOR DURING BACKFILL, AND COMPACTION OVER THE STYROFOAM SM SHEETS SHALL MEET THE COMPRESSIVE STRENGTH REQUIREMENTS OF ASTM D1621-73 AND SHALL BE AS MANUFACTURED BY DOW CHEMICAL COMPANY, MIDLAND, MICHIGAN, OR EQUAL. IN NO CASE SHALL THE SEWER LINES HAVE LESS THAN FOUR (4') FEET OF COVER OVER THE TOP OF THE PIPE.

F. LEAKAGE TESTS AND ALLOWANCES FOR GRAVITY SEWERS:

THE LOW PRESSURE AIR TEST WILL BE USED TO SIMULATE INFILTRATION OR EXFILTRATION RATES INTO OR OUT OF ALL GRAVITY SEWERS. THE CONTRACTOR WILL FURNISH ALL FACILITIES AND PERSONNEL FOR CONDUCTING THE TEST. FINAL ACCEPTANCE OF THE SEWER SHALL DEPEND UPON THE SATISFACTORY PERFORMANCE OF THE SEWER UNDER TEST CONDITIONS. THE TEST SHALL BE PERFORMED ON PIPE BETWEEN ADJACENT MANHOLES AFTER BACKFILLING HAS BEEN COMPLETED AND COMPACTED.

ALL WYES, TEES, LATERALS, OR END-OF-SIDE SEWER STUBS SHALL BE PLUGGED WITH FLEXIBLE-JOINT CAPS, OR AN ACCEPTABLE ALTERNATE, SECURELY FASTENED TO WITHSTAND THE INTERNAL TEST PRESSURE. SUCH PLUGS OR CAPS SHALL BE READILY REMOVABLE, AND THEIR REMOVAL SHALL PROVIDE A SOCKET SUITABLE FOR MAKING A FLEXIBLE-JOINTED LATERAL CONNECTION OR EXTENSION.

PRIOR TO TESTING FOR ACCEPTANCE, THE PIPE SHOULD BE CLEANED BY PASSING THROUGH THE PIPE A FULL GAUGE SQUEEGEE. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO HAVE THE PIPE CLEANED. IMMEDIATELY FOLLOWING THE PIPE CLEANING, THE PIPE INSTALLATION SHALL BE TESTED WITH LOW-PRESSURE AIR.

AIR SHALL BE SLOWLY SUPPLIED TO THE PLUGGED AIR INSTALLATION UNTIL THE INTERNAL AIR PRESSURE REACHES FOUR POUNDS PER SQUARE INCH (4.0 PSI) GREATER THAN THE AVERAGE BACK PRESSURE OF ANY GROUNDWATER THAT MAY SUBMERGE THE PIPE. AT LEAST TWO MINUTES SHALL BE ALLOWED FOR TEMPERATURE STABILIZATION BEFORE PROCEEDING FURTHER.

THE PIPELINE SHALL BE CONSIDERED ACCEPTABLE WHEN TESTED AT AN AVERAGE PRESSURE OF THREE POUNDS PER SQUARE INCH (3.0 PSI) GREATER THAN THE AVERAGE BACK PRESSURE OF ANY GROUNDWATER THAT MAY SUBMERGE THE PIPE IF:

1. THE TOTAL RATE OF AIR LOSS FROM ANY SECTION TESTED IN ITS ENTIRETY BETWEEN MANHOLE AND CLEANOUT STRUCTURES DOES NOT EXCEED 2.0 CUBIC FEET PER MINUTE; OR 2. THE SECTION UNDER TEST DOES NOT LOSE AIR AT A RATE GREATER THAN 0.0030 CUBIC FEET PER MINUTE PER SQUARE FOOT OF INTERNAL PIPE SURFACE.

THE REQUIREMENTS OF THIS SPECIFICATION SHALL BE CONSIDERED SATISFIED IF THE TIME REQUIRED IN SECONDS FOR THE PRESSURE TO DECREASE FROM 3.5 OR 2.5 PSI GREATER THAN THE AVERAGE BACK PRESSURE OF ANY GROUNDWATER THAT MAY SUBMERGE THE PIPE IS NOT LESS THAN THAT COMPUTED ACCORDING TO THE FOLLOWING TABLE:

MINIMUM TEST TIME FOR VARIOUS PIPE SIZES DIAMETER (SEC./100 FT.) (INCHES

THE TABLE GIVES THE REQUIRED TEST TIME IN SECONDS PER 100 FOOT LENGTHS OF PIPE FOR A GIVEN DIAMETER. IF THERE IS MORE THAN ONE PIPE SIZE IN THE SECTION OF LINE BEING TESTED, COMPUTE THE TIME FOR EACH DIAMETER; AND SUM THE TIMES TO FIND THE TOTAL REQUIRED TEST TIME.

IF THE PIPE INSTALLATION FAILS TO MEET THESE REQUIREMENTS, THE CONTRACTOR SHALL DETERMINE AT HIS OR HER OWN EXPENSE THE SOURCE OR SOURCES OF LEAKAGE AND SHALL REPAIR (IF THE EXTENT AND TYPE OF REPAIRS PROPOSED BY THE CONTRACTOR APPEAR REASONABLE TO THE ENGINEER) OR REPLACE ALL DEFECTIVE MATERIALS OR WORKMANSHIP. THE COMPLETED PIPE INSTALLATION SHALL MEET THE REQUIREMENTS OF THIS TEST BEFORE BEING CONSIDERED ACCEPTABLE.

SINCE THIS TEST DOES NOT DETERMINE THE TIGHTNESS OF MANHOLES, THEY SHALL BE TESTED SEPARATELY. THE EXFILTRATION LEAKAGE ALLOWANCE OUT OF MANHOLES SHALL BE NO GREATER THAN ONE GALLON PER DAY PER VERTICAL FOOT TO DEPTH. THE MANHOLE SHALL BE FILLED WITH WATER TO A POINT ONE FOOT (1') ABOVE THE HIGHEST POINT BETWEEN MANHOLE SECTIONS. IN AREAS OF HIGH GROUNDWATER, THERE SHALL BE NO VISIBLE LEAKAGE DUE TO INFILTRATION. IF A VACUUM TEST IS DESIRED. THE FOLLOWING PROCEDURE SHALL BE FOLLOWED: THIS PREFERRED METHOD OF TESTING MANHOLES FOR LEAKAGE INVOLVES THE USE OF A DEVICE FOR SEALING THE TOP OF THE MANHOLE CONE SECTION AND PUMPING AIR OUT OF THE MANHOLE, CREATING A VACUUM AND HOLDING THIS VACUUM FOR A PRESCRIBED PERIOD OF TIME.)

1. ALL LIFTING HOLES AND EXTERIOR JOINTS SHALL BE FILLED AND POINTED WITH AN APPROVED NON-SHRINKING MORTAR. THE COMPLETED MANHOLE SHALL NOT BE BACKFILLED PRIOR TO TESTING. MANHOLES WHICH HAVE BEEN BACKFILLED SHALL BE EXCAVATED TO EXPOSE THE ENTIRE EXTERIOR PRIOR TO VACUUM TESTING OR THE MANHOLE SHALL BE TESTED FOR LEAKAGE BY MEANS OF A HYDROSTATIC TEST. REPAIRS SHALL ONLY BE MADE TO THE EXTERIOR OF THE MANHOLE.

2. ALL PIPE AND OTHER OPENINGS INTO THE MANHOLE SHALL BE SUITABLY PLUGGED IN A MANNER TO

3. A PLATE WITH AN INFLATABLE RUBBER RING THE SIZE OF THE TOP OF THE MANHOLE SHALL BE INSTALLED BY INFLATING THE RING WITH AIR TO PRESSURE ADEQUATE TO PREVENT LEAKAGE OF AIR BETWEEN THE RUBBER RING AND MANHOLE WALL. 4. AIR SHALL THEN BE PUMPED OUT OF THE MANHOLE THROUGH AN OPENING IN THE PLATE UNTIL A VACUUM IS CREATED INSIDE OF THE MANHOLE EQUAL TO TEN INCHES (10") OF MERCURY ON AN APPROVED VACUUM GAUGE. THE REMOVAL OF AIR SHALL THEN BE STOPPED AND THE TEST TIME BEGUN.

5. THE VACUUM MUST NOT DROP TO BELOW NINE INCHES (9") OF MERCURY WITH A TWO MINUTE TEST PERIOD. IF MORE THAN A ONE INCH (1") DROP IN VACUUM OCCURS WITHIN THE TWO MINUTE TEST PERIOD, THE MANHOLE HAS FAILED AND SHALL BE REPAIRED OR RECONSTRUCTED AND THEN RETESTED.

6. FOLLOWING SATISFACTORY TEST RESULTS, THE MANHOLE MAY BE BACKFILLED. IT IS NOTED THAT ALL EXISTING SANITARY SEWERS SHALL BE KEPT OPERATIONAL UNTIL NEW WORK HAS BEEN TESTED AND APPROVED BY THE ENGINEER. AT SUCH TIME, EXISTING SEWERS AND SEWER SERVICES SHALL BE CONNECTED TO THE NEW SEWERS.

G. LEAKAGE AND PRESSURE TESTING FOR FORCE MAIN ALL PIPELINES SHALL BE TESTED IN ACCORDANCE WITH THE VERMONT DEPARTMENT OF WATER RESOURCES ENVIRONMENTAL PROTECTION RULES, LATEST EDITION. A LEAKAGE AND PRESSURE TEST SHALL BE PERFORMED

THE HYDROSTATIC TEST PRESSURE SHALL BE A MINIMUM OF 50 PSI AT THE HIGHEST POINT ALONG THE TEST SECTION AND SHALL NOT VARY BY MORE THAN FIVE PSI DURING THE ENTIRE TWO HOUR TEST. IF AND WHEN DURING THE TEST THE PRESSURE DROPS BY FIVE PSI, THE QUANTITY OF WATER REQUIRED TO RESTORE THE TEST PRESSURE SHALL BE MEASURED.

AT THE END OF THE TWO HOUR TEST, THE PRESSURE SHALL BE RETURNED TO THE TEST PRESSURE AND THE ADDITIONAL VOLUME OF WATER MEASURED. THE TOTAL AMOUNT OF WATER USED DURING AND AT THE END OF THE TEST SHALL CONSTITUTE THE ACTUAL LEAKAGE. THE MAXIMUM ALLOWABLE LEAKAGE SHALL BE DETERMINED

L = SD(P) /133,200 L = LEAKAGE IN GALLONS PER HOUR = DIAMETER OF PIPE IN INCHES P = AVERAGE TEST PRESSURE IN PSI

S = LENGTH OF PIPE BEING TESTED

H. CLEANING PIPELINES AND APPURTENANCES:

UPON COMPLETION OF CONSTRUCTION, ALL DIRT AND OTHER FOREIGN MATERIAL SHALL BE REMOVED FROM PIPELINES AND THEIR APPURTENANT CONSTRUCTIONS. NO MATERIALS SHALL BE LEFT IN THE PIPELINES TO IMPEDE NORMAL FLOW THROUGH THEM.

WHERE REQUIRED ON THE PLANS, SEWER SERVICE CONNECTIONS FOR ONE HOUSE SHALL BE CONSTRUCTED OF SIX INCH (6") PIPE UNLESS OTHERWISE NOTED ON THE PLANS OF THE TYPE MATERIAL SPECIFIED UNDER THIS SECTION. THE PIPE SHALL BE LAID AND ITS JOINTS MADE AS REQUIRED FOR SEWER CONSTRUCTION IN THIS

OPEN ENDS OF PIPES SHALL BE PROPERLY SEALED TO PREVENT DAMAGE AND INTRUSION OF FOREIGN MATTER WHERE HOOKUP TO THE BUILDING SEWER IS NOT COINCIDENT WITH SEWER MAIN CONSTRUCTION. ADDITIONALLY, THE CONTRACTOR WILL PROVIDE A PVC PIPE TEMPORARY MARKER APPROVED BY THE ENGINEER FROM THE SEWER SERVICE INVERT UP TO TWENTY-FOUR INCHES (24") ABOVE THE FINISHED GRADE. THE MARKER SHALL BE SEATED SECURELY INTO THE GROUND FOR EASE IN RELOCATING THE END OF SEWER SERVICE CONNECTION FOR HOOKING UP THE BUILDING SEWER.

IN THE CASE OF RECONNECTION OF EXISTING SERVICES, SUCH RECONNECTIONS WILL BE MADE ONLY AFTER THE NEW SEWER MAIN HAS BEEN COMPLETED, TESTED, AND ACCEPTED. THE EXCAVATION, BEDDING MATERIAL, INSTALLATION, AND BACKFILL FOR SERVICE CONNECTIONS SHALL BE THE SAME AS FOR SEWER MAINS.

J. CLEANOUTS FOR SEWERS:

CLEANOUTS FOR GRAVITY SEWERS AND FORCE MAINS SHALL BE PROVIDED EVERY 100 FT OR WHERE THE SUM OF BENDS = 45 DEGREES. CLEANOUT FRAMES AND COVERS SHALL BE OF TOUGH GRAY CAST IRON. CASTINGS SHALL BE TRUE TO PATTERN AND FREE FROM FLAWS. THE BEARING SURFACE OF CLEANOUT FRAMES AND COVERS AGAINST EACH OTHER SHALL BE MACHINED TO GIVE CONTINUOUS CONTACT THROUGHOUT THEIR CIRCUMFERENCE. ALL IRON CASTINGS SHALL BE THOROUGHLY CLEANED AND THEN COATED WITH HOT COAL TAR BEFORE BEING DELIVERED.

GENERAL WATER SPECIFICATIONS


- CONTRACTOR SHALL CONTACT ALL UTILITIES BEFORE EXCAVATION TO VERIFY THE LOCATION OF ANY UNDERGROUND LINES. THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT 1-800-DIG-SAFE PRIOR TO ANY EXCAVATION. UTILITIES INFORMATION SHOWN ON THESE PLANS WERE OBTAINED FROM THE BEST AVAILABLE SOURCE AND MAY OR MAY NOT BE EITHER BE ACCURATE OR COMPLETE. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY DAMAGE TO ANY UTILITY, PUBLIC OR PRIVATE, SHOWN OR NOT SHOWN HEREON.
- 2. THE HORIZONTAL AND VERTICAL SEPARATION FOR SEWER AND WATER LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE LATEST EDITION OF THE "VERMONT WATER SUPPLY RULE".
- THE WATER MAINS SHALL BE CONSTRUCTED, TESTED, AND DISINFECTED IN ACCORDANCE WITH AWWA STANDARDS C-600 AND C-651 WITH THE EXCEPTION OF THE TABLET METHOD OF DISINFECTION. THE CONTRACTOR SHALL FURNISH ALL GAUGES, TESTING PLUGS, CAPS, AND ALL OTHER NECESSARY EQUIPMENT AND LABOR TO PERFORM LEAKAGE, PRESSURE AND DISINFECTION TESTS IN SECTIONS OF AN APPROVED LENGTH. EACH VALVED SECTION OR A MAXIMUM OF ONE THOUSAND FEET (1,000') OF THE PIPE SHALL BE TESTED. WATER REQUIRED FOR TESTING SHALL BE POTABLE. ALL TESTING SHALL BE CONDUCTED IN THE PRESENCE OF THE ENGINEER.

FOR THE PRESSURE TEST, THE CONTRACTOR SHALL DEVELOP AND MAINTAIN 200 POUNDS PER SQUARE INCH FOR TWO HOURS. FAILURE TO HOLD THE DESIGNATED PRESSURE FOR THE TWO-HOUR PERIOD CONSTITUTES A FAILURE OF THE SECTION TESTED. THE LEAKAGE TEST SHALL BE PERFORMED CONCURRENTLY WITH THE PRESSURE TEST. DURING THE TEST, THE CONTRACTOR SHALL MEASURE THE QUANTITY OF WATER REQUIRED TO MAINTAIN THE TEST PRESSURE. LEAKAGE SHALL NOT EXCEED THE QUANTITY GIVEN BY:

- L = SD (SQUARE ROOT OF P) / 148,000
- L = LEAKAGE IN GALLONS/HOUR = LENGTH OF PIPELINE TESTED
- = DIAMETER OF PIPE IN INCHES P = AVERAGE TEST PRESSURE IN PSI

ALL TESTING SHALL BE CONDUCTED IN ACCORDANCE WITH AWWA C600 LATEST REVISION. SHOULD ANY SECTION OF THE PIPE FAIL EITHER THE PRESSURE OR LEAKAGE TESTS, THE CONTRACTOR SHALL DO EVERYTHING NECESSARY TO LOCATE AND REPAIR OR REPLACE THE DEFECTIVE PIPE. FITTINGS. OR JOINTS AT NO EXPENSE TO THE OWNER. IF, FOR ANY REASON, THE ENGINEER SHOULD ALTER THE FOREGOING PROCEDURES, THE CONTRACTOR SHALL REMAIN RESPONSIBLE FOR THE TIGHTNESS OF THE LINE WITH THE ABOVE REQUIREMENTS. THE METHOD OF DISINFECTION SHALL BE BY THE CONTINUOUS FEED METHOD UNLESS OTHERWISE APPROVED BY THE ENGINEER. AFTER FILLING, FLUSHING. AND THE INITIAL ADDITION OF CHLORINE SOLUTION. THE FREE CHLORINE CONCENTRATION WITHIN THE PIPE SHALL BE AT LEAST 20 MG/L. THE CHLORINATED WATER SHALL REMAIN IN THE MAIN FOR A PERIOD OF AT LEAST 24 HOURS. AT THE END OF THIS PERIOD, THE TREATED WATER IN ALL PORTIONS OF THE MAIN SHALL HAVE A RESIDUAL OF NOT LESS THAN 10 MG/L FREE CHLORINE. ALL DISINFECTION SHALL BE PERFORMED UNDER THE SUPERVISION OF THE ENGINEER. THE DISINFECTION PROCESS SHALL BE DEEMED ACCEPTABLE ONLY AFTER SAMPLES OF WATER FROM THE FLUSHED, DISINFECTED MAIN TAKEN BY THE ENGINEER AND TESTED AT AN APPROVED LABORATORY SHOW NO EVIDENCE OF BACTERIOLOGICAL CONTAMINATION. DISINFECTION SHALL CONFORM TO THE LATEST AWWA C651 REVISION. THE PIPELINE AND APPURTENANCES SHALL BE MAINTAINED IN AN UNCONTAMINATED CONDITION UNTIL FINAL ACCEPTANCE. DISINFECTION SHALL BE REPEATED WHEN AND WHERE REQUIRED AT NO EXPENSE TO THE OWNER UNTIL FINAL ACCEPTANCE BY THE OWNER.

- ALL NEW WATER MAIN PIPE SHALL BE OF THE SIZE AND TYPE SHOWN ON THE PLANS. ALL C900 PVC PIPE IS TO BE CLASS DR14 WITH A PRESSURE RATING OF 305 PSI. PVC PIPE SHALL BE IN ACCORDANCE WITH AWWA C-901. ALL FITTINGS SHALL BE CEMENT-LINED DUCTILE IRON, 350 POUNDS WORKING PRESSURE. AND CONFORM TO AWWA C-104, C-111, AND C-110 OR C-153 FOR COMPACT FITTINGS. MECHANICAL JOINT NUTS AND BOLTS SHALL BE HIGH STRENGTH, LOW ALLOY STEEL PER ANSI A-21.11. ALL CURB STOPS AND CORPORATION STOPS SHALL MEET AWWA C-800 STANDARDS.
- 5. ALL HYDRANTS SHALL BE KENNEDY MODEL K-81D MEULLER SUPER CENTURION 250 AND CONFORM TO AWWA C-502 WITH A 5 1/4" VALVE OPENING, A MECHANICAL JOINT INLET, A 6" MECHANICAL JOINT SHOE, AND BE LEFT OPENING WITH NATIONAL STANDARD THREADS AND 4" STORZ CONNECTION. THE CONTRACTOR SHALL PROVIDE AND INSTALL AN AUXILIARY VALVE OF THE TYPE INDICATED ON THE CONTRACT DRAWINGS AND A LENGTH OF 6" DUCTILE IRON PIPE SUFFICIENT TO CONNECT THE HYDRANT TO THE MAIN.
- ALL GATE VALVES SHALL BE CEMENT-LINED AND MEET THE REQUIREMENTS OF AWWA C-509. ALL VALVES SHALL BE MECHANICAL JOINT, CAST IRON BODY, PARALLEL BRASS SEATS, NON-RISING STEM, INSIDE SCREW,
- RESILIENT SEAT CONSTRUCTION WITH O-RING STEM SEALS. 7. ALL WATER MAIN THRUST BLOCKS SHALL BE CONSTRUCTED OF 3,500 PSI CONCRETE.
- 8. THE WATER MAINS SHALL HAVE A MINIMUM DEPTH OF COVER OF 6'.
- 9. ANY SURFACES, LINES, OR STRUCTURES WHICH HAVE BEEN DAMAGED BY THE CONTRACTOR'S OPERATIONS SHALL BE RESTORED TO A CONDITION AT LEAST EQUAL TO THAT IN WHICH THEY WERE FOUND IMMEDIATELY PRIOR TO THE BEGINNING OF CONSTRUCTION.
- 10. THE CONTRACTOR SHALL COORDINATE THE LOCATION AND INSTALLATION OF THE INDIVIDUAL LOT WATER LINE SERVICES WITH THE OWNER AT THE TIME OF CONSTRUCTION.
- 11. THE CONTRACTOR SHALL USE "MEGALUG" RESTRAINTS ON ALL M.J. FITTINGS.
- 12. ALL MAIN LINE GATE VALVES SHALL BE BEDDED IN A MINIMUM OF 6" OF 3/4" 1" STONE. CONCRETE SHALL NOT BE USED.
- 13. PRIOR TO ISSUANCE OF A CERTIFICATE OF OCCUPANCY FOR THE 1ST NEW UNIT, THE EXISTING WATER SERVICES, CURB STOPS AND EXISTING WATER METERING INFRASTRUCTURE MUST BE UPGRADED TO THE TOWN OF ESSEX



TYPICAL SHARED WATER SYSTEM

ROADWAY, PARKING

PROPERTY LINE

BUILDINGS

SURFACE WATER

SEWAGE SYSTEM:

DOWNSLOPE WELL

UPSLOPE WELL

DRIVES, < 3 RESIDENCES

SEWAGE PIPING / TANKS

SLOPE EARTH AWAY FROM WELL CASING ELECTRICAL -SERVICE CONDUIT MINIMUN CABLE -1-1/2" SCH. 40 PVC -PITLESS ADAPTOR OR APPROVED EQUAL GROUT FOR MIN. 15' BELOW PITLESS -ADAPTER. GROUT SHOULD EXTEND AT LEAST 10' INTO WEATHERED BEDROCK -BEDROCK-CASING SHOULD **EXTEND AT LEAS** 10' INTO SOLID ROCK SUBMERSIBLE PUMP TYPICAL SHARED DRILLED WELL

-SCREENED VENT

DRILLED WELL ISOLATION DISTANCES SHARED DRILLED WELL DESIGN DATA

25 FEET

15 FEET

50 FEET

10 FEET


10 FEET


10 FEET


200 FEET

100 FEET

- 1. THE DRILLED WELL(S) CONSTRUCTION, LOCATION, DISINFECTION AND TESTING SHALL BE IN ACCORDANCE WITH THE STATE OF VERMONT - WATER SUPPLY
- 2. THE BASIS OF DESIGN FOR THE DRILLED WELL IS
- A. AVG. DAY DEMAND: 1,400 GPD (5 x 2-BEDROOM UNITS) B. MAX. DAY DEMAND : 1,400 GPD/720 MIN/DAY = 1.94 GPM C. INSTANTANEOUS PEAK DEMAND: 5 GPM X 5 UNITS = 25 GPM
- D. SOURCE CAPACITY: TO BE DETERMINED E. STORAGE CAPACITY: SIZE TO BE DETERMINED BASED ON WELL YIELD (IF REQUIRED)
- F. PUMP CAPACITY AT UNITS: 5 UNITS @ 5 GPM = 25 GPM MINIMUM G. OPERATING PRESSURE RANGE; 40 - 60 PSI AT PRESSURE SWITCH







1	DATE	REVISION	
	SURVEY OBCA DESIGN	☐ RECORD DRAWING ☐ PRELIMINARY ☐ SKETCH/CONCEPT	
	BWC GRT DRAWN GRT	O'LEARY-BURKE CIVIL ASSOCIATES, PLC	
	BWC SCALE 1" = 40'	13 CORPORATE DRIVE ESSEX JUNCTION, VT 05452 PHONE: 802-878-9990 FAX: 802-878-9989 E-MAIL: obca@olearyburke.com	١

WATER AND SEWER DETAILS AND SPECIFICATIONS

MULCHING SPECIFICATIONS

DISTURBED AREAS ARE TO BE MULCHED WITHIN A WEEK OF DISTURBANCE. HAY MULCH SHALL BE SPREAD UNIFORMLY OVER THE AREA AT A RATE OF TWO TONS PER ACRE OR AT A RATE THAT IS SUFFICIENT TO PROVIDE ADEQUATE COVERAGE.

WITHIN 48 HOURS OF FINAL GRADING, THE EXPOSED SOIL MUST BE SEEDED AND MULCHED.

SNOW MANAGEMENT PLAN:

FOLLOWING THE ACCUMULATION OF ANY SNOW FALL EVENT WHICH GENERATES MORE THAT 1" OF SNOW OR ICE THE SITE SHALL BE CLEARED AND ALL SNOW AND ICE STORED IN THE IDENTIFIED SNOW STORAGE AREAS ON THE EPSC CONSTRUCTION PLANS. ALL SNOW STORAGE AREAS SHALL BE DOWN GRADIENT OF ANY DISTURBED AREAS AND THE STORAGE OF SNOW IN STORMWATER TREATMENT STRUCTURES IS PROHIBITED.

WINTER CONSTRUCTION REQUIREMENTS

- ALL WORK SHALL BE IN ACCORDANCE WITH THE LOW RISK SITE HANDBOOK FOR EROSION PREVENTION AND SEDIMENT CONTROL.
- PROVIDE ENLARGED ACCESS POINTS, STABILIZED TO PROVIDE FOR SNOW STOCKPILING.
- 3. A MINIMUM 25 FT BUFFER SHALL BE MAINTAINED FROM PERIMETER CONTROLS SUCH AS SILT FENCE.
- 4. DRAINAGE STRUCTURES MUST BE KEPT OPEN AND FREE OF SNOW AND ICE DAMS.
- 5. SILT FENCE AND OTHER PRACTICES REQUIRING EARTH DISTURBANCE MUST BE INSTALLED AHEAD OF FROM GROUND.
- 6. MULCH USED FOR TEMPORARY STABILIZATION MUST BE APPLIED AT DOUBLE THE STANDARD RATE,
- OR A MINIMUM OF 3 INCHES WITH AN 80-90% COVER.

 7. TO ENSURE COVER OF DISTURBED SOIL IN ADVANCE OF A MELT EVENT, AREAS OF DISTURBED SOIL MUST BE STABILIZED AT THE END OF EACH WORK DAY, WITH THE FOLLOWING EXCEPTIONS:
 - IF NO PRECIPITATION WITHIN 24 HOURS IS FORECAST AND WORK WILL RESUME IN THE SAME DISTURBED AREA WITHIN 24 HOURS, DAILY STABILIZATION IS NOT NECESSARY.
- DISTURBED AREAS THAT COLLECT AND RETAIN RUNOFF, SUCH AS HOUSE FOUNDATIONS OR OPEN UTILITY TRENCHES.
 PRIOR TO STABILIZATION, SNOW OR ICE MUST BE REMOVED TO LESS THAN 1 INCH THICKNESS.

OR WHERE CONSTRUCTION VEHICLE TRAFFIC IS ANTICIPATED. STONE PATHS SHOULD BE 10-20

FEET WIDE TO ACCOMMODATE VEHICULAR TRAFFIC.

10. IN AREAS OF DISTURBANCE THAT DRAIN TO A WATER BODY WITHIN 100 FEET, TWO ROWS OF SILT FENCE MUST BE INSTALLED ALONG THE CONTOUR.

9. USE STONE TO STABILIZE AREAS SUCH AS THE PERIMETER OF BUILDINGS UNDER CONSTRUCTION

WINTER INSPECTION SCHEDULE	AFTER A THAW OR A RAINFALL GENERATING RUNOFF FROM SITE
INSPECT SILT FENCING WITH SKI TAPE	X
INSPECT AREAS TEMPORARILY MULCHED	X
INSPECT TEMPORARY STOCKPILES	X
INSPECT STABILIZED CONSTRUCTION ENTRANCES	X
INSPECT AREAS THAT HAVE BEEN TOPSOILED & MULCHED	X
INSPECT STORMWATER SWALES, SPREADERS, OUTFLOW DEVICES	X

STUMP DISPOSAL SPECIFICATIONS

ALL SUITABLE TREES THAT MUST BE CUT WILL BE USED AS FIREWOOD. THE STUMPS, BRUSH, & EXCESS UNSUITABLE EARTH WILL BE DISPOSED OF AT THE LOCATION DESIGNATED BY THE ENGINEER, CONTINGENT UPON APPROVAL FROM THE TOWN BUILDING INSPECTOR. SAID AREA(S) SHALL BE A MINIMUM OF TWO FEET ABOVE THE SEASONAL HIGH GROUNDWATER OR THE STUMPS SHALL BE HAULED OFF-SITE TO A STATE-APPROVED LANDFILL. IF ON-SITE STUMP DISPOSAL IS IMPLEMENTED, THE FOLLOWING GUIDELINES SHALL BE MET:

- WHENEVER POSSIBLE, STUMP DISPOSAL SITES SHOULD BE LOCATED ON NEARLY LEVEL TO MODERATELY SLOPING LANDS (SLOPES LESS THAN 12%).
- 2. DISPOSAL SITES WILL NOT BE LOCATED IN OR WITHIN 100 FEET OF FLOWING
- WATERCOURSES OR STREAMS OR IN ACTIVELY ERODING GULLIES.

 3. DISPOSAL SITES SHALL NOT BE LOCATED IN FLOODED OR FLOOD—PRONE LANDS, MARSHES, OR OTHER AQUIFER RECHARGE AREAS.
- 4. STUMPS WILL BE PLACED ON THE SITE IN A SINGLE LIFT PRIOR TO BACKFILLING. WHEN ADDITIONAL STUMPS ARE TO BE DEPOSITED ON THE SAME SITE, EACH SUCCESSIVE
- LAYER OR LIFT OF STUMPS WILL BE BACKFILLED.

 5. STUMPS DEPOSITED IN DRAINAGEWAYS OR DEPRESSIONS SHALL BE BACKFILLED AND
- BERMED SO AS TO DIVERT OVERLAND FIRE DISPOSAL AREA.
- 6. A MINIMUM OF TWO FEET (2') OF OVERBURDEN WILL BE PLACED OVER ALL DISPOSAL SITES.

 7. THE TWO FEET OF OVERBURDEN WILL BE COVERED WITH A MINIMUM OF FOUR INCHES
- 7. THE TWO FEET OF OVERBURDEN WILL BE COVERED WITH A MINIMUM OF FOUR INCHES (4") OF TOPSOIL, GRADED, SEEDED, AND MULCHED IN ACCORDANCE WITH THE

EROSION CONTROL SPECIFICATIONS

- SEE OTHER DRAWINGS OF THESE PLANS FOR ADDITIONAL STORMWATER AND EROSION CONTROL SPECIFICATIONS AND DETAILS.
- 2. THE ROADWAY AND YARD FINISH GRADE SLOPES SHALL NOT BE STEEPER THAN 3 ON 1. THE FINISHED GRADE SLOPES SHALL BE IMMEDIATELY GRADED AND MULCHED.
- 3. ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEEDING
 AND MULCHING PRIOR TO NOVEMBER 1 OF EACH YEAR. ANY DISTURBED AREAS OUTSIDE
- OF THE ROADWAY SHALL BE IMMEDIATELY SEEDED AND MULCHED WITHIN 15 DAYS.

 4. THE EROSION CONTROL METHODS USED DURING CONSTRUCTION OF THE DEVELOPMENT SHALL
- PROCEED IN THE FOLLOWING SEQUENCE:

 A) THE CONTRACTOR SHALL INSTALL AND MAINTAIN SILT FENCES, AND OTHER EROSION CONTROL MEASURES, IF REQUIRED, AS ORDERED BY THE ENGINEER. THE EROSION CONTROL MEASURES SHALL BE MAINTAINED AND REPAIRED AFTER EVERY RAINFALL UNTIL THE NEW IMPROVEMENTS ARE PAVED AND ALL DISTURBED AREAS HAVE BEEN GRASSED. THE REPAIR

OF THE EROSION CONTROL MEASURES WILL INCLUDE REMOVING ANY SEDIMENTATION. THE

SEDIMENT MAY BE PLACED AS FILL IN THE LOW AREAS, IF APPROVED BY THE ENGINEER

- B) THE TOPSOIL SHALL BE REMOVED FROM THE AREAS TO BE GRADED AND STOCKPILED. A SILT FENCE SHALL BE PLACED CONTINUOUSLY AROUND THE BOTTOM OF THE PILE.
- C) IN AREAS NEAR THE NEW CONSTRUCTION, THE CONTRACTOR SHALL ENCLOSE THE TRUNKS OF TREES TO BE SAVED WITH WOODEN SNOW FENCING ALONG THE DRIPLINE TO PROTECT THE FROM INJURY.
- D) THE SITE GRADING AND BUILDING/UTILITY INFRASTRUCTURE SHALL BE CONSTRUCTED. THE CONTRACTOR WILL INSTALL INLET PROTECTION AROUND THE CATCH BASINS UNTIL THE ROADWAY HAS BEEN PAVED AND GRASS HAS BEEN ESTABLISHED ON THE SLOPES.
- E) THE CONTRACTOR WILL TOPSOIL, SEED, AND MULCH THE DISTURBED AREAS AS SOON AS POSSIBLE FOLLOWING COMPLETION OF ADJACENT CONSTRUCTION.
- F) OPEN CUT AREAS SHALL BE MULCHED OUTSIDE OF ACTUAL WORK AREAS, AND SILT FENCE SHALL BE EMPLOYED TO CONFINE SHEET WASH AND RUNOFF TO THE IMMEDIATE OPEN AREA AS ORDERED BY THE ENGINEER.
- DURING CONSTRUCTION, THE PROJECT SHALL BE IN COMPLIANCE WITH THE LOW RISK SITE HANDBOOK FOR EROSION PREVENTION AND SEDIMENT CONTROL.


LANDSCAPING SPECIFICATIONS

ALL DISTURBED AREAS SHALL BE STABILIZED WITH SEEDING AND MULCHING PRIOR TO NOVEMBER 1 OF EACH YEAR. ANY DISTURBED AREAS SHALL BE IMMEDIATELY SEEDED AND MULCHED WITHIN 15 DAYS. ANY WORK PERFORMED AFTER NOVEMBER 1 OF EACH YEAR SHALL BE STABILIZED WITH MULCH OR NETTING SUFFICIENT TO PREVENT EROSION AND SHALL BE IMMEDIATELY SEEDED AND REMULCHED AS SOON AS WEATHER PERMITS IN THE SPRING. ALL DISTURBED AREAS SHALL RECEIVE A MINIMUM OF 4" OF TOPSOIL AND BE SEEDED, FERTILIZED, LIMED, AND MULCHED IN ACCORDANCE WITH THE

- 1. SEED MIXTURE IN ALL AREAS SHALL BE URBAN MIX CONFORMING TO THE TABLE SHOWN ON THE PLANS. FOR SEEDING BETWEEN SEPTEMBER 1 AND NOVEMBER 1, WINTER RYE SHALL BE USED AT AN APPLICATION RATE OF 100 POUNDS PER ACRE.
- 2. FERTILIZER SHALL BE STANDARD COMMERCIAL GRADE CONFORMING TO THE STATE FERTILIZER LAW AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. DRY FERTILIZER, IF USED, SHALL BE APPLIED AT THE RATE OF 500 POUNDS PER ACRE. LIQUID FERTILIZER, IF USED, SHALL BE APPLIED IN A 1-2-1 RATIO WITH THE MINIMUM RATE TO INCLUDE 100 POUNDS OF NITROGEN, 200 POUNDS OF PHOSPHATE, AND 100 POUNDS OF POTASH PER ACRE.
- 3. LIMESTONE SHALL CONFORM TO ALL STATE AND FEDERAL REGULATIONS AND TO THE STANDARDS OF THE ASSOCIATION OF OFFICIAL AGRICULTURAL CHEMISTS. THE LIMESTONE SHALL BE APPLIED AT A RATE OF TWO TONS PER ACRE OR AS DIRECTED.
- WITHIN 24 HOURS OF APPLICATION OF FERTILIZER, LIME, AND SEED, THE SURFACE SHALL BE MULCHED WITH A HAY MULCH. MULCH SHALL BE SPREAD UNIFORMLY OVER THE AREA

URBAN MIX GRASS SEED				
% BY WEIGHT	LBS. LIVE SEED PER ACRE	TYPE OF SEED		
37.5	45	CREEPING RED FESCUE		
31.25	37.5	KENTUCKY BLUEGRASS		
31.25	37.5	WINTER HARDY, PERENNIAL RYE		
100	120 # LIVE SEED PER ACRE			

AT A RATE OF TWO TONS PER ACRE OR AS ORDERED BY THE ENGINEER.



NOTES:

1. THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OF SEDIMENT ONTO PUBLIC RIGHTS—OF—WAY. THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT.


- ALL SEDIMENT TRACKED, SPILLED, OR WASHED ONTO PUBLIC RIGHTS—OF—WAY SHALL BE REMOVED IMMEDIATELY BY THE CONTRACTOR.


 2. THE USE OF CALCIUM CHLORIDE OR WATER MAY BE NECCESSARY TO CONTROL
- DUST DURING DRY PERIODS.


 3. PROVIDE APPROPRIATE TRANSITION BETWEEN CONSTRUCTION ENTRANCE AND THE EXISTING ROADWAY


STABILIZED CONSTRUCTION ENTRANCE

NTS










FABRIC TO BE KEYED 6" INTO GROUND

NOTE: USE ONLY MANUAL METHODS OF INSTALLATION AND CLEANING WITHIN WETLAND AND BUFFER ZONE.

TEMPORARY SILT FENCE



TEMPORARY FILL MATERIAL STOCKPILE

NTS

No. 018.0114132

DATE	REVISION	
SURVEY OBCA	☐ RECORD DRAWING ☐ PRELIMINARY ☐ FINAL ☐ SKETCH/CONCEPT	
BWC GRT	O'LEARY-BURKE	
GRT CHECKED	CIVIL ASSOCIATES, PLC 13 CORPORATE DRIVE	
BWC SCALE	ESSEX JUNCTION, VT 05452 PHONE: 802-878-9990	
1" = 40'	FAX: 802-878-9989 E-MAIL: obca@olearyburke.com	

NTS

THE CONTRACTOR SHALL NOTIFY "DIGSAFE" AT

1-888-DIG-SAFE PRIOR TO ANY EXCAVATION.

STORM SYSTEM MAINTENANCE

MAINTENANCE PLAN

SYSTEM MAINTENANCE IS IMPORTANT FOR TREATMENT AND CONTROL OF STORM RUNOFF FROM THE IMPERVIOUS SURFACES (ROAD, PARKING, BUILDING AND WALKWAY). THE FOLLOWING ELEMENTS FORM THE MINIMUM

1. THE OWNER (OR REPRESENTATIVE) SHALL PERFORM INSPECTIONS ANNUALLY AND FOLLOWING SIGNIFICANT (LARGE) STORM EVENTS. THE FOLLOWING ITEMS SHALL BE REVIEWED: CONDITION OF THE VEGETATION, CONDITION OF THE DITCH SURFACES, DEPTH OF ACCUMULATED SEDIMENT (IF ANY), THE PRESENCE OF EROSION (IF ANY), CONDITION OF THE STORM PIPES, AND THE CONDITION OF THE PIPE INLETS AND OUTLETS. ANY OBSERVABLE DEGRADATION OF THE STORM SYSTEM SHALL BE NOTED.

2. THE OWNER (OR REPRESENTATIVE) SHALL COMPLETE REPAIR OF ANY ITEMS, AS REQUIRED TO MAINTAIN OPTIMAL SYSTEM OPERATION. AT A MINIMUM, THE FOLLOWING ITEMS SHALL BE INCLUDED:


A. ANY EROSION GULLIES 6 INCHES OR DEEPER SHALL BE FILLED AND VEGETATION ESTABLISHED IN THE DISTURBED

B. SEDIMENT ACCUMULATED TO A DEPTH OF MORE THAN 6 INCHES IN THE ROAD DITCHES SHALL BE REMOVED AND DISPOSED OF IN AN UPLAND AREA THAT IS NOT WITHIN 100 FEET OF WATERS OF THE STATE. VEGETATION SHALL BE ESTABLISHED IN ALL DISTURBED AREAS.

C. VEGETATION SHALL BE ESTABLISHED AS NEEDED, IN AREAS OF BARE SOIL. THIS IS PARTICULARLY IMPORTANT IN FLOW AREAS WHERE VEGETATION PROVIDES SEDIMENT REMOVAL.


D. SILT FENCES SHALL BE USED IF NEEDED TO PREVENT EROSION AND AID IN THE ESTABLISHMENT OF VEGETATION. THESE TEMPORARY MEASURES SHALL BE REMOVED AFTER THE SITE IS STABILIZED AND THE RISK OF EROSION IS

E. THE GRASSED AREAS SHALL BE MOWED AS NEEDED TO PREVENT THE ESTABLISHMENT OF WOODY VEGETATION.




- 1. THE CONTRACTOR SHALL AT ALL TIMES KEEP THE TRENCHES ENTIRELY FREE OF WATER UNTIL ALL WORK IS
- 2. REFER TO THE WRITTEN SPECIFICATIONS FOR BACKFILL AND COMPACTION REQUIREMENTS.
- 3. REFER TO THE WRITTEN SPECIFICATIONS FOR STORM DRAINAGE PIPE REQUIREMENTS.
- 4. THE SIDES OF THE TRENCHES 4 FEET OR MORE IN DEPTH TO BE ENTERED BY PERSONNEL SHALL BE SHEETED, SLOPED, OR PROPERLY SUPPORTED, CONFORMING TO VOSHA REQUIREMENTS.
- 5. PIPE BEDDING SHALL BE CRUSHED STONE, FROM 6" BELOW THE INVERT, TO THE SPRINGLINE OF THE PIPE.





GRASS DRAINAGE SWALE



DRY POND/OUTLET STRUCTURE DETAIL

3. SEE PLANS FOR POND, PIPE, CHANNEL, WEIR, AND BASIN LOCATIONS.

4. FOREBAY SEDIMENT SHALL BE REMOVED EVERY 10 YEARS OR WHEN FOREBAY VOLUME IS REDUCED BY 50%.


TOP OF POND 50% WQV FOREBAY INFLOW PIPE ->,' STORMWATER TREATMENT AREA Roadway underdrain

SEDIMENT FOREBAY DETAIL

1) CONTRACTOR SHALL SUB-CUT THE INFILTRATION AREA AS SHOWN ON THE PLANS. WHERE POSSIBLE, EXCAVATION SHOULD BE PERFORMED WITH A BACKHOE AND WORK SHOULD BE DONE FROM THE SIDES AND OUTSIDE THE FOOTPRINT OF THE INFILTRATION AREA TO AVOID SOIL COMPACTION. IF IT IS NECESSARY TO WORK IN THE INFILTRATION AREA, ONLY LOW GROUND PRESSURE TRACKED EQUIPMENT SHOULD BE ALLOWED TO COMPLETE THE WORK, RUBBER TIRE EQUIPMENT SHALL BE STRICTLY PROHIBITED WITHIN THE INFILTRATION AREA, UNLESS WORKING FROM PAVEMENT OUTSIDE OF THE BASIN OR TRENCH. THE CONTRACTOR SHALL START THE WORK AT THE FAR SIDE OF THE TRENCH OR BASIN AND WORK THEIR WAY OUT.

2) SUBSOIL DECOMPACTION IS REQUIRED IN ALL INFILTRATION AREAS, DECOMPACT SUBSOIL WITH A BACKHOE RIPPER ATTACHMENT OR OTHER APPROVED METHOD TO A DEPTH OF AT LEAST 18 INCHES

3) THE CONTRACTOR SHALL TOPSOIL, SEED, AND MULCH THE DISTURBED AREAS AS SOON AS POSSIBLE FOLLOWING COMPLETION OF ADJACENT CONSTRUCTION. TOPSOIL SHALL MEET THE POST-CONSTRUCTION SOIL DEPTH AND QUALITY STANDARD.



Raise frame to finished grade only after base course of pavement is in place — raise frame to base course grade if wear course is to be placed during the following construction season.


4000 psi concrete by SD IRELAND, CAMP PRECAST or approved equal.

Flexible manhole sleeves shall be provided for all pipe penetrations.

Backfill structure with Granular backfill VAOT 703.04

STRUCTURE SHALL BE H20 RATED WITHIN ROADWAYS

CATCH BASIN DETAIL



DATE		REVISION		
URVEY		RECORD DRAWING	PRELIMINARY	
OBCA		FINAL	SKETCH/CONCEPT	
ESIGN			_	
BWC G	RT	O'LEARY	Z-RURKF	
RAWN		_	_	
GRT		CIVIL ASSO	CIATES, PLC	
HECKED				
3WC		13 CORPORATE DRIVE ESSEX JUNCTION. VT 05452		
CALE			- /	
1" = 40'		PHONE: 802-878-9990 FAX: 802-878-9989 E-MAIL: obca@olearyburke.com		

HOMESTEAD CAMPGROUND GEORGIA, VERMONT

STORMWATER DETAILS AND **SPECIFICATIONS**

Legend **BOUNDARY LINE ABUTTER LINE** SPLIT AIL FENCE (PVC) CONCRETE MONUMENT FOUND IRON PIPE FOUND PK NAIL WITH BRASS DISK IRON BAR FOUND IRON BAR SET A.G ABOVE GRADE B.G **BELOW GRADE** FLUSH СВ CHORD BEARING CHORD DISTANCE UNMONUMENTED CORNER, NO MARKER FOUND OR SET

GENERAL SURVEY NOTES

1. The purpose of this plan is to depict the re-subdivision of the property known as 864 Ethan Allen Highway in Georgia, Vermont.

- 2. Reference is made to the following plats and plans recovered within the Town of Georgia Land Records
- **a.** "ALTA/ACSM Land Title Survey and Boundary Line Adjustment, DG Strategic II, LLC, Portion of Lands of S. T. Mack Inc, Volume 151, Page 738" 864 Ethan Allen Highway, Georgia, Vermont, sheet 1 of 2," dated 9-26-12, last revised 4-23-14, by Button Professional Land Surveyors, P.C. as recorded in Slide 230A of the Town of Georgia Land Records.
- **b.** "ALTA/ACSM Land Title Survey, DG Strategic II, LLC, Volume 262, Page 246", 864 Ethan Allen Highway, Georgia, Vermont, sheet 1 of 2,"dated 10-27-14, by Button Professional Land Surveyors, P.C. as recorded in Slide ??? of the Town of Georgia Land Records.
- **c.** "ALTA/ACSM Land Title Survey, Dearborn Land Investment LLC, Portion of Lands of S. T. Mack Inc, Volume 151, Page 738", 864 Ethan Allen Highway, Georgia, Vermont, sheet 1 of 2, dated 9-28-12, last revised 8-8-13, by Button Professional Land Surveyors, P.C. as recorded in Slide 228A of the Town of Georgia Land Records.
- d. "ALTA/ACSM Land Title Survey, Dearborn Land Investment LLC, Portion of Lands of S. T. Mack Inc, Volume 151, Page 738",864 Ethan Allen Highway, Georgia, Vermont, Sheet 2 of 2" dated 9-28-12, last revised 8-8-13, by Button Professional Land Surveyors, P.C. as recorded in Slide 228B of the Town of Georgia Land Records.
- **e.** Sheet 2 of Project Georgia ST 237 M as prepared by the State of Vermont Department of Highways, undated as filed with the Vermont Agency of Transportation.
- **f.** Sheet 9 of 12 of Project Georgia BP 237 M as prepared by the State of Vermont Department of Highways, undated as filed with the Vermont Agency of Transportation.
- g. Sheet 9 of 12 of Project Georgia BP 019-5 6676 as prepared by the State of Vermont
- Department of Highways, undated as filed with the Vermont Agency of Transportation.
- h. "Arrowhead Lake Village, (Property Plat West)Vermont Route 104A, Georgia, Vermont", dated 7-11-94, as prepared by Lamoureux & Dickinson and recorded in slide 185 of the Town of Georgia Land
- i. "Arrowhead Lake Village, (Property Plat East)Vermont Route 104A, Georgia, Vermont", dated 7-11-94, as prepared by Lamoureux & Dickinson and recorded in slide 185A of the Town of Georgia Land
- j. "Plat of Survey, Raymond & Ethel Bovat Property, 11.04 acres"
- as prepared by Warren A. Robenstien, L.S. dated November, 1982 and recorded in slide 150 of the Town of Georgia Land Records.
- **k.** "David M. & Julie M. Malloy property" as prepared by John E. Buck dated 12 May, 1966 and recorded in slide 41 of the Town of Georgia Land Records.
- I. "Meadowood Park, Proposed Five Lot Subdivision", as prepared by JHStuart, dated Feb, 1986 and recorded in slide 105 of the Town of Georgia Land Records.
- m. "Myott Subdivision" as prepared by David A. Tudhope L.S., dated 5-17-08, and recorded in slide 192 of the Town of Georgia Land Records.
- **3.** The variable Rights-of-Way widths for Route 7 and Route 104A are based on the plans referenced in notes 1E-G above.
- **4.** This property was conveyed to 864 Ethan Allen Highway, LLC.by deed recorded in Vol. 316, Pgs 289-290 of the Town of Georgia Land Records.
- **5.** The key deed for this property is recorded in Vol. 151, Pg 738 of the Town of Georgia Land Records.
- **6.** All iron bars set are $\frac{5}{8}$ " iron bars with aluminum caps marked OBCA property corner , LS 656. all monumentation found is as noted.
- 7. This property may be subject to other easements or rights of way.
- **8.** Bearings shown on this plat are based on the Vermont State Plane Coordinate System and are given in U.S. Survey Foot values (NAD83 (2011), VT-4400). Bearings were determined by Network RTK-GPS observations made on site January 25, 2024.

